

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-12973-0000

LEASE NAME Smallwood Unit

WELL NUMBER #2

990 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 2 TWP. 22 RGE. 14 (E) or (W)

COUNTY Stafford

Date Well Completed 9-24-51

Plugging Commenced 8-23-89

Plugging Completed 9-26-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rockhold Engineering, Inc.

ADDRESS Box 698, Great Bend, Kansas 67530

PHONE 816-793-5290 OPERATORS LICENSE NO. 5111

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 25, 1989 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 3810'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	340'	None
				5-1/2"	3810'	2,704.75'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet set.
Dumped sand to 3440' and 5 sacks cement. Shot casing at 3000' and 2700' pulled 88 Jts
of 5 1/2" casing. BJ. Titan plugged well with 400# hulls 10 sacks gel, 50 sacks cement
10 sacks gel, 100# hulls released plug and pumped 100 sacks 60/40 pozmix with 6%
gel, Maximum pressure was 400 psi and shutin 350 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rockhold Engineering, Inc. RECEIVED

STATE OF Kansas COUNTY OF Barton, ss.

STATESMAN 10-9-89
OCT 09 1989

James W. Rockhold (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well, as filed the
the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 6th day of October, 1989

My Commission Expires:

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appl. Exp. 9-26-89

Notary Public