

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
30 S. Market, Room 2078  
Topeka, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 06-05-45

LEASE NAME Wilson

WELL NUMBER 1

330 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 1 TWP. 22 RGE. 14W (E) or (W)

COUNTY Stafford

Date Well Completed 06-05-45

Plugging Commenced 12-31-97

Plugging Completed 12-31-97

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Big "O"

ADDRESS 2820 Paseo Drive, Great Bend, Kansas 67530

PHONE (316) 876-5305 OPERATORS LICENSE NO. 3942

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-31-97 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top 3437' Bottom 3596 T.D. 3775'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Pipe			8 5/8"	385'	-0-
	Production			5 1/2"	3713'	440'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Ran 2 3/8" tubing to 790', circulated. Allied mixed 210 sacks 60/40 6% gel cement- tubing stuck- did not circulate cement. Backed off 2 3/8" @ 240', ran 2 3/8" tubing back to 300'. Mixed 90 sacks 60/40 6% gel cement, circulated, pulled tubing out and topped off with 10 sacks.  
Job started 12:50 pm completed 3:00 pm

RECEIVED  
STATE CORPORATION COMMISSION  
License No. 6901

JAN 8 1998 1-8-98

Name of Plugging Contractor D. S. & W. Well Servicing, Inc.

Address P. O. Box 231, Claflin, Kansas 67525

CONSERVATION DIVISION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Orville Monroe


STATE OF Kansas COUNTY OF Barton, ss.

Arthur P. Strube (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Arthur P. Strube

(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED AND SWORN TO before me this 5th day of January, 19 98



Bonnie Combs  
Notary Public

Expires: April 8, 2001