

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-10913-0000

LEASE NAME Bordewick

WELL NUMBER 4

_____ Ft. from S Section Line

_____ Ft. from E Section Line

100' S NE NE NE
SEC. 1 TWP. 22S RGE. 14 (X) or (W)

COUNTY Stafford

Date Well Completed 6-10-53

Plugging Commenced 5-17-89

Plugging Completed 5-26-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Route 3, Box 20 A, Great Bend, Ks. 67530

PHONE# (316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 1, 1989 (date)

by Shari Feist Albrecht (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? -

Producing Formation LKC Depth to Top 3378 Bottom 3614 T.D. 3640

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

6-8-89
RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
Lansing-Kansas City	Oil & Water	3378	3614	8 5/8	376.38'	0
				5 1/2"	3637	0

JUN - 8 1989

CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set CIBP at 3350'. Dump 1 sack cement w/bailer on top of CIBP. Perforate 5 1/2" casing at 850' in Anhydrite with 2' squeeze gun. Pump in 3 sacks gel, pump 340 sacks 60-40 Pozmix, 6% gel circulated cement out 8 5/8 - 5 1/2 annulus. Shut in annulus, pump 20 sacks cement down 5 1/2" casing. Max pressure 350 PSI. Shut in pressure 50 PSI. Filled well with 2 sacks cement.
(If additional description is necessary, use BACK of this form.) (OVER)

Name of Plugging Contractor Phillips Petroleum Company License No. 5229

Address Route 3, Box 20A, Great Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Phillips Petroleum Company

STATE OF Kansas COUNTY OF Barton, ss.

A. R. Lyons (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) K.E. [unclear] for A.R. LYONS

(Address) Route 3, Box 20-A, Great Bend, KS

SUBSCRIBED AND SWORN TO before me this 7th day of June, 19 89

My Commission Expires: 10-23-92

Notary Public
NOTARY PUBLIC - State of Kansas
CARLA M. YAHNE
My Appt. Exp. 10-23-92

cut off 8 5/8" casing. Welded steel plate showing company name, well name and date plugged.

EXPLORATION RECORD

Lease **Bordwick**

Well **A**

Formation Name	Top	Base	Remarks
Sand	0	85	
Sand, shale and shells	85	280	
Sand	280	373	
Bedded	373	480	
Shale and shells	480	784	
Anhydrite	784	808	
Shale and shells	808	940	
Shale, shells, salt	940	1251	
Shale, and shells	1251	1605	
Lime	1605	1840	
Lime and shale	1840	1977	
Lime	1977	2045	
Shale	2045	2080	Elevation: 1918 D.F.
Shale and shells	2080	2170	
Lime	2170	2190	Top:
Shale and shells	2190	2210	Hebner 3213
Shale and lime	2210	2745	Toronto 3261
Shale	2745	2765	Douglas 3277
Lime	2765	2905	Brown
Lime and shale	2905	2975	Limestone 3366
Lime	2975	3213	LHC 3378
Shale	3213	3240	Base LHC 3414
Lime and shale	3240	3249	Viola 3436
Shale, lime and shells	3249	3313	Rotary TD 3440
Shale and lime	3313	3340	
Lime	3340	3415	
Shale	3415	3424	
Lime	3424	3440	

Elevation: 1918 D.F.

Top:

Hebner 3213
 Toronto 3261
 Douglas 3277
 Brown

Limestone 3366
 LHC 3378
 Base LHC 3414
 Viola 3436
 Rotary TD 3440

Penetrated producing formation
 or LHC 3378; plugged back
 to 3454.

- 1 - Bvils
- 1 - G. A. Daniels
- 1 - P. W. Shelton
- 1 - File
- 1 - Geological Bvils Division Office
- 1 - Geological District Office

RECEIVED
 STATE CORPORATION COMMISSION

JAN 30 1989

CONSERVATION DIVISION
 Wichita, Kansas

RECEIVED
 STATE CORPORATION COMMISSION

JAN 26 1939

CONSERVATION DIVISION
 Wichita, Kansas