


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800-Sitting Building
Wichita, Kansas

Stafford County, Sec. 1 Twp. 22 Rge. 14 (E) (W)
Location as "NE/CNWKSWK" or footage from lines NE/4 NE/4 NW/4
Lease Owner Republic Natural Gas Company
Lease Name Bordewick Well No. 3
Office Address Box 126, Ellinwood, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed September 18 1954
Application for plugging filed September 24 1954
Application for plugging approved Verbal approval from M. A. Rives 9-18-54
Plugging commenced September 18 1954
Plugging completed September 18 1954
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Depth to top Bottom Total Depth of Well 3820 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	310'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- 3820' - 270 Rotary mud
- 270' - Bridge plug with 1/2 sacks of hulls on top
- 270' - 30 20 sacks cement
- 30' - Bridge plug with 1/2 sack of hulls on top
- 30' - surface - 10 sacks cement

Conservation Division
Wichita, Kansas
9-25-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones Drilling Company
Address 507 Orpheum Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Barton ss.
P. B. Horst (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) P. B. Horst
Box 126, Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of September 24, 1954

My commission expires 8-20-55
Yvonne M. Stevenson Notary Public.

PLUGGING
FILED SEC. 1 T. 22 R. 14 W
BOX PAGE 64 LINE 59

GABBERT-JONES DRILLING COMPANY
WICHITA, KANSAS
DRILLERS WELL LOG

BORDEWICK #3
 NE NE NW SECTION 1-22-14W
 STAFFORD COUNTY, KANSAS
 COMMENCED 9-7-54
 COMPLETED 9-18-54

DEPTH		FORMATION	REMARKS
FROM	To		
0	40	SURFACE CLAY & SAND	
40	220	SAND & SHALE	
220	310	SHALE & SHELLS	RAN 310 FEET OF 10 3/4" CASING, CEMENTED W/250 BAGS CEMENT.
310	810	SHALE & SHELLS	
810	840	ANHYDRITE	
840	1240	SHALE, SHELLS & SALT	
1240	1675	SHALE & SHELLS	
1675	1875	SHALE	
1875	1915	LIME	
1915	2465	LIME & SHALE	
2465	2690	SHALE & SHELLS	
2690	2840	SHALE	
2840	3467	LIME & SHALE	
3467	3545	LIME	
3545	3591	LIME & SHALE	
3591	3631	LIME	
3631	3765	CHERTY LIME & SHALE	
3765	3801	CONGLOMERATE	
3801	3820	CHERTY LIME & SHALE	
3820	TD		DRY & ABANDONED

EXECUTED THIS 21ST DAY OF SEPTEMBER, 1954

C. J. Gabbert

STATE OF KANSAS }
 COUNTY OF SEDGWICK) 58

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 21st DAY OF September, 1954 PERSONALLY APPEARED C. J. Gabbert TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES 10-27-54

Sumner S. Hall
 NOTARY PUBLIC

PLUGGING
 FILE SEC 1 T22 R14W
 BOOK PAGE 64 LINE 39