

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
209 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-205 5

LEASE NAME Gartung

WELL NUMBER 3

3410 Ft. from S Section Line

4400 Ft. from E Section Line

SEC. 4 TWP. 22 RGE. 14 (X) or (W)

COUNTY Stafford

Date Well Completed 3-20-70

Plugging Commenced 9-29-93

Plugging Completed 9-29-93

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Condor Energy, Inc.

ADDRESS PO Box 108 Great Bend, Kansas 67530

PHONE# (316) 792-1340 OPERATORS LICENSE NO. 6016

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-25-92 (date)

by W. Rankin (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckle-Viola Depth to Top 3751 Bottom 3839 T.D. 3839

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil	3822	3839	8 5/8	452	0
Viola	Oil	3750		5 1/2	3836	2356

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Open hole and perfs sanded back to approx 3650 and 5 sx cement spotted at 3650.  
Mixed 300# hulls - 10 sx gel - 50 sx cement - 10 sx gel - 100# hulls - 150 sx cement.  
600 # max pressure - shut in 200 # max pressure

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Condor Energy, Inc. License No. 6016

Address PO Box 108 Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Condor Energy, Inc.

STATE OF Kansas COUNTY OF Barton, ss.


Jim Davis (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim Davis

(Address) PO BOX 108 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 19th day of Oct., 1993

Delores L. Stetson  
Notary Public



Commission Expires: May 2, 1992