


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 12 Twp. 22 Rge. (E) 13 (W)  
Location as "NE/CNW/SW" or footage from lines SE SW NW  
Lease Owner Strata Drilling, Inc.  
Lease Name Curtis Well No. 1  
Office Address Box 355 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 17, 19 57  
Application for plugging filed August 26, 19 57  
Application for plugging approved 19  
Plugging commenced August 16, 19 57  
Plugging completed August 17, 19 57  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Brundage - Hoisington  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3721' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	262	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with 1/3 sacks hulls, 20 sacks cement at 240'. 1/3 sacks hulls and 10 sacks cement at 40'. Job completed 8-17-57 at 7:00 A.M.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.  
Address Box 355 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Jim B. McWilliams (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim B. McWilliams  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of August, 19 57  
Robert E. Southern  
Notary Public.

My commission expires November 9, 1959

PLUGGING  
FILE SEC 12 T. 22 R. 13w  
BOOK PAGE 38 LINE 3

8-27-57  
CONSERV.  
WELL

DRILLERS LOG

# 1 Curtis

CASING RECORD: 262' of used 8-5/8" surface casing  
 COMPANY: Strata Drilling, Inc.  
 DESCRIPTION: SE SW NW Sec. 28-18-9W Stafford Co., Kansas

TOTAL DEPTH: 3721'  
 CONTRACTOR: Strata Drilling, Inc.  
 COMMENCED: August 7, 1957  
 COMPLETED: August 17, 1957

ELEVATION: 1715' DF  
 1712' GL

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface soil and sand	0	145	Ran 13 Jts. (262') used 8-5/8" surface casing; cemented with 200 sacks cement, 4% c.c.
Sand and Shale	145	252	
Red Bed and Shale	252	680	
Anhydrite	680	705	
Shale and Shells	705	1260	
Lime and shale	1260	3185	DST # 4. 3713'-3721'. Tool open 30 Min.. Recovered 25' mud. BHP-0
Lime	3185	3716	
TOTAL DEPTH 3716'			

Top Anhydrite	685'	
Top Heebner	3199'	(-1312)
Top Brown Line	3333'	(-1446)
Top Lansing	3352'	(-1465)
Base Kansas City	3561'	(-1674)
Top Viola	3608'	(-1721)
Top Simpson	3647'	(-1760)
Top Arbuckle	3703'	(-1813)

STATE OF KANSAS )  
 COUNTY OF BARTON )      ss:

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Jim B. McWilliams*  
 JIM B. McWILLIAMS, Sec-Tres.

Subscribed and sworn to before me this 22nd day of August, 1957.

*Robert E. Southern*  
 Notary Public

My Commission Expires:  
November 9, 1959

**PLUGGING**  
 FILE SEC 12 T. 22 R. 13W  
 BOOK PAGE 30 LINE 3

RECEIVED  
 COMMISSION  
 AUG 27 1957  
 COMMISSION DIVISION  
 Wichita, Kansas