

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Hodgeman SEC. 21 TWP. 22S RGE. 22W E/W  
Location as in quarters or footage from lines:  
SE NW


Lease Owner Sun Oil Company  
Lease Name Lingenfelder #1 Well No. \_\_\_\_\_  
Office Address Box 67 Hays, Kansas 67601  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 1-19-82  
Plugging completed 1-28-82  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durant  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4525'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				9-5/8"	255'	none
				7"	4524'	2482'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 75 sacks cement on bottom. Shot pipe @3613', 3100', 3004', 2906', 2815', 2689', 2598' and 2498'. Pulled a total of 79 joints of pipe. Plugged well with 2 sacks hulls, 15 sacks gel, 1 sack hulls, 70 sacks 50/50 pos, 4% gel, 2% cc., 15 sacks gel, plug, 70 sacks 50/50 pos, 4% gel, 2% cc. Plugging Complete.

2-5-82

RECEIVED  
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Kelso Casing Pulling FEB - 15 1982


STATE OF Kansas COUNTY OF Rice, ss. CONSERVATION DIVISION  
Wichita, Kansas

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 176 Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of February, 19 82

My Commission expires:




Irene Hoover  
Notary Public.

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Hodgeman County, Sec. 21 Twp. 22S Rge. 22 ~~W/W~~  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C-SE/4 of NW/4 - 660' FSL & 660' FEL  
Lease Owner Sun Exploration & Production Co.  
Lease Name Emma Lingenfelder Well No. 1  
Office Address P. O. Box 35567-Tulsa, Oklahoma 74135  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Oil



Locate well correctly on above  
Section Plat

Date Well completed October 19 82  
Application for plugging filed July 27 19 81  
Application for plugging approved Aug. 11 & Nov. 5 19 81  
Plugging commenced January 15 19 82  
Plugging completed March 5 19 82  
Reason for abandonment of well or producing formation  
Depleted - No potential recompletion  
If a producing well is abandoned, date of last production  
March 19 81

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant  
Producing formation Mississippi Depth to top 4435 Bottom 4455 Total Depth of Well 4525'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Oil	4435	4455	7"	4524'	2498'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Circulate hole clean. Spot 25 Sx. cement plug at 4415'. Spot 50 Sx. cement plug at 4375'. Pull tbg. up to 4000'. Waiting on csg. pullers. Work 7" csg. to 165,000#. Could not pull free. Shot csg. at 3616'. Work to 165,000# could not pull free. Shot csg. 3100' Work to 165,000#. Could not pull free. Shot csg. 3000'. Work to 165,000#. Could not pull free. Shot csg. 2889'. Work to 365,000#. Could not pull free. Shot csg. 2598'. Work to 165,000#. Could not pull free. Shot csg. 2498'. Pull out of hole w/2498' of 7" csg. Flowed 40 Bbl. salt wtr. while pulling csg. Killed well w/4 Sx. hulls, 140 Sx. Pozmix. Waiting on top plug. Dug out & cut off 9-5/8" surface csg. 4' below GL. Fill w/6 Sx. cement. Weld on steel plate. Back fill cellar & clean up lcoation.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton & Kelso Casing Pullers

RECEIVED  
STATE CORPORATION COMMISSION

MAR 22 1982

STATE OF Oklahoma COUNTY OF Tulsa  
S. Weaver (employee of owner) ~~owner or operator~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

S. Weaver  
P. O. Box 35567-Tulsa, Oklahoma 74135

(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of March, 19 82

Maureen Wiley

Notary Public.

My commission expires October 2, 1983