


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

NORTH



Locate well correctly on above  
Section Plat

Hodgman County. Sec. 21 Twp. 22 Rge. 22 (E) (W)  
Location as "NE/CNW/SW" or footage from lines NE SE  
Lease Owner R. W. Lange  
Lease Name E. Miller #2 Well No.  
Office Address Garden City, Kansas 67846  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 4/15/71 19  
Plugging completed 4/21/71 19  
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eves  
Producing formation Depth to top Bottom Total Depth of Well 4440' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	272	none
				4 1/2"	4426	3192'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4440', ran sand to 4400' and dumped 4 sacks of cement. Rigged up over 4 1/2", well started to flow, had welder and water truck out. Cut head off and weld on collar. Put control head on and collar leaked, removed head and welded collar again, rigged up over 4 1/2", shot pipe at 3798', 3609', 3415', 3225', 3190', pulled 101 joints. Allied pumped 5 sacks mud and 2 sacks hulls, 80 sacks of cement from 850 to 550', 8 mud from 550 to 270', 30 cement from 270 to 170', 2 mud from 170 to 40', 10 cement from 40 to 0.

PLUGGING COMPLETE.

5-13-71

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 13 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
CHASE, KANSAS  
(Address)

Subscribed and sworn to before me this 22nd day of April, 1971

MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

Margaret Melcher  
Notary Public.

EXHIBIT 4 cont.

E. Miller #2 Lease  
 NE SE Section 21 - T22S - R22W  
 Hodgeman County, Kansas

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 14 1971  
 CONSERVATION DIVISION  
 Wichita, Kansas

8 5/8" Casing - 24#	272.06' - 13 joints @ 268 w/200 sacks common cement 3% HA-5 T.D. 4440'
4 1/2" Casing - 9.5#	4432.43' - 140 joints @ 4426 w/100 sacks salt saturated Pozmix
2" Tubing	4450' ± - 140 joints
# 319 Sucker Rods w .05 (4375')	175 - 3/4" x 25'
Polished Rod	1 - 1 1/4" x 16' with liner
Pony Rods	1 - 3/4" x 2' 1 - 3/4" x 4' 1 - 3/4" x 8' 1 - 3/4" x 10'
Stuffing Box	2" Hercules
Pump	2" x 1 1/2" x 14" RWT Insert
Guiberson Shorty Tension Packer	