


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Hodgman County, Sec. 21 Twp. 22 Rge. 22 (E) (W)
SW NW
Location as "NE/CNWSW" or footage from lines _____
Lease Owner: Braden Deem, Inc.
Lease Name: A. Miller Unit #1 Well No. _____
Office Address: Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced: 9/25/72 _____ 19____
Plugging completed: 2/21/73 _____ 19____
Reason for abandonment of well or producing formation: depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well: Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well: 4458 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	263	none
				5 1/2"	4445	3495'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole to 4435', set 5 sacks cement. Shot pipe at 2678', 2585', 2491', pulled 113 joints. Allied pumped 8 sacks gel, 70 sacks cement, 7 sacks gel and 50 sacks cement to plug well.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: KNIGHT CASING PLUGGING CO., INC.
Address: CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 1st day of March, 19 73

My commission expires _____

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Notary Public.

WELL LOG

15-083-10252-0000

COMPANY SUNRAY D-X OIL COMPANY

SEC. 21 T. 22S R. 22W

FARM A. MILLER UNIT NO. 1


LOC. C-SW, NW

TOTAL DEPTH 4458'

COUNTY HODGEMAN CO., KANSAS

COMM. December 14, 1962 COMP. December 24, 1962

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 263' w/224 sax.
5 1/2" @ 4445' w/125 sax.

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

264	Surface clay, shale & sand
744	Shale, sand & red bed
762	Blaine anhydrite
832	Red bed
1025	Sand
1368	Red bed & shale
1402	Anhydrite
1545	Shale
2310	Shale & shells
2664	Lime
2765	Lime & shale
2915	Shale
3801	Shale & lime
3920	Lime & shale
4389	Lime
4423	Lime & shale
4458	Lime
4458	T. D.

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1972
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #1 A. MILLER UNIT well.

Verne A. Morris

Subscribed and sworn to before me this 11th day of January 1963

My Commission Expires: October 24, 1966

Beaufort
NOTARY PUBLIC