

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,826-0000

LEASE NAME Golden Belt

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR L. D. Drilling, Inc.

SEC. 23 TWP. 22 RGE. 14 (EVEN/W)

ADDRESS R.R. 1, Box 183B Great Bend, Ks. 67530

COUNTY Stafford

PHONE (316) 793-3051 OPERATORS LICENSE NO. 6039

Date Well Completed

Character of Well Oil

Plugging Commenced 5-31-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-4-96

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3870'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	302'	none
				5 1/2"	3869'	2412'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Plugged off bottom with sand to 3546' and 5 sacks cement. Shot pipe at 3015', 2618' and 2412'. Pulled casing. Pumped 300# hulls, 10 sacks gel, 50 sacks cement, 100# hulls, 10 sacks gel, 150 sacks cement. 60/40 6% gel Max pres. 600# Shut in @300 PSI Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L. D. Drilling, Inc. -Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P.O. Box 209 Chase, Kansas 67524.

SUBSCRIBED AND SWORN TO before me this 5th day of June, 19 96

Irene Herzberg
Notary Public

My Commission Expires:



CONSERVATION DIVISION
WICHITA, KS

JUL 06 1996

RECEIVED
STATE CORPORATION COMMISSION

7-6-96