

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford

County. Sec. 23 Twp. 22 Rge. 14W(E) (W)

Location as "NE/CNW*SW*" or footage from lines NW/4

Lease Owner Lawrence Supply Company

Lease Name George Well No. 1

Office Address Box 448 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed March 30 19 54

Application for plugging approved 19

Plugging commenced April 3 19 54

Plugging completed April 12 19 54

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives

Producing formation Depth to top Bottom Total Depth of Well 3789 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	240'	None
				5-1/2"	3777'	2004'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with sand from 3789' to 3770' and ran 5 sacks of cement. Pumped in 25 sacks of jell mud and bailed hole to 250'. Set a rock bridge from 250' to 240' and ran 20 sacks of cement. Mudded hole to 35', set a 10' rock bridge and ran 10 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
P. B. Lawrence (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Lawrence Supply Co.
(Signature) P. B. Lawrence

SUBSCRIBED AND SWORN TO before me this 28th day of April, 1954

My commission expires Sept. 15, 1956
Matter J. Volk Notary Public.

24-7368-6 3-53-20M

PLUGGING
FILED SEC 23 TWP 22 R 14W
BOOK PAGE 24 LINE 12

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1954 4-29-54
CONSERVATION DIVISION
Wichita, Kansas