

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County. Sec. 23 Twp. 22 Rge. 14 (E)X (W)  
Location as "NE/CNW/SW" or footage from lines NW NW NW  
Lease Owner Bert Maxwell et al  
Lease Name Hoffmaster Well No. 1  
Office Address 1623 E. Douglas; Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 10 19. 50  
Application for plugging filed " " 19. 50  
Application for plugging approved " " 19. 50  
Plugging commenced " " 19. 50  
Plugging completed " " 19. 50  
Reason for abandonment of well or producing formation Dry

NORTH

Section Plat grid with 4 columns and 4 rows.

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19...  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Hollis  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 5 3/8", 513'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to... feet for each plug set.

Filled hole with heavy mud to 120 feet. Set wooden plug at 120 feet.  
Pumped 15 sacks of cement on top of plug thru drill pipe. Filled hole with heavy mud to 25 feet. Set wooden plug and dumped 10 sacks of cement on top of plug.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Brunson Drilling Company, Inc.  
Address 333 First National Bank Bldg.; Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Ralph B. McLaughlin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BRUNSON DRILLING COMPANY, INC.

(Signature) Ralph B. McLaughlin  
333 1st National Bank Bldg.; Wichita, Ks. (Address)

SUBSCRIBED AND SWORN to before me this 18th day of November, 19. 50

My commission expires September 23, 1953

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 20 1950  
O. Combs Notary Public  
11-20-50

PLUG  
FILE SEC 23 T 22 R 14 W  
BOOK PAGE 48 LINE 35

## BERT MAXWELL ET AL

Well: Hoffmaster #1

NW/NW/NW Section 23-22-14  
Stafford County, KansasCommenced RD: 10/30/50  
Completed DD: 11/10/50  
Total Depth: 3512'Elevation: 1932' R.B.  
Initial Prod: Dry  
Contractor: Brunson Drilling Co., Inc.

Casing: 513' 8 5/8" O.D. 8rd thd 24#

<u>STRATA</u>	<u>DEPTH</u>	
Surface Soil & Sand	70	
Sand & Gravel	260	
Gravel	305	
Shale & Gyp.	320	
Redbeds	335	
Sand	490	
Redbeds	515	
Redbed	822	
Anhydrite	850	
Shale & Shells	1035	
Shale	1700	
Lime	1730	
Broken Lime	1880	
Lime - Sandy	1980	
Lime	2205	
Lime - Sandy	2280	
Lime & Shale	2425	
Shale & Lime	2795	
Broken Lime	2890	
Lime & Shale	2980	
Shale & Lime	3050	
Broken Lime	3122	
Lime & Shale	3187	
Lime	3255	
Broken Lime	3315	
Lime	3435	
Lime & Shale	3492	
Lime	3512	
Total Depth	3512	
		<u>TOPS:</u>
		Heebner Shale 3307
		Brown Lime 3437
		Lansing - K. C. 3448

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

BRUNSON DRILLING COMPANY, INC.  
By

RECEIVED  
NOV 20 1950  
KANSAS CORPORATION COMMISSION

*Ralph B. McLaughlin*  
Ralph B. McLaughlin, Asst. Sec.

Signed and sworn to in my presence this 18th day of November, 1950, by Ralph B. McLaughlin, asst. secretary of the Brunson Drilling Company, Inc., a corporation in the State of Kansas.

*Edwina C. Combs*  
Notary Public

My commission expires September 23, 1953.

