


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 23 Twp. 22S Rge. 14W (XXXXXX)
Location as "NE/CNW/SW" or footage from lines 380' FEL and 315' FNL
Lease Owner Phillips Petroleum Company
Lease Name Staff Well No. 1
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed January 11, 1950 19
Application for plugging filed January 14, 1960 19
Application for plugging approved January 18, 1960 19
Plugging commenced January 25, 1960 19
Plugging completed January 28, 1960 19
Reason for abandonment of well or producing formation Uneconomical to operate



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production January 18, 1960 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot
Producing formation LKC Depth to top 3441 Bottom 3678 Total Depth of Well PB 3689 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Dry	3300		8-5/8	423.26	None
Toronto	Dry	3320		5-1/2	3827.26	2741'
Brown Lime	Dry	3430				
LKC	Oil	3441				
Base LKC		3678				
Viola	Dry	3714				
Simpson	Dry	3759				
Arbuckle	Oil	3803				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole from 3440' to 300'. Set rock bridge to 290'. Dumped 20 sx cement to 230'. Mudded to 40'. Set rock bridge to 30'. Dumped 10 sx cement in filling to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 2 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co.
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Phillips
Box 779, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of January, 1960

My commission expires 11-18-61

Notary Public.



R

EXPLORATION RECORD

Lease _____ Staff _____

Well 1

Formation Name	Top	Base	Remarks
Sand, Clay	0	70	
Sand and Shells	70	315	
Shells and Red Bed	315	443	Elevation: 1929' Ground
Red Bed, Sand and Shells	443	953	1932' DF
Shale and Shells	953	1515	
Shale, Lime and Shells	1515	1703	
Lime	1703	1824	
Lime and Shale	1824	2346	
Shale	2346	2539	
Lime and Shale	2539	2675	
Shale	2675	2788	
Lime and Shale	2788	3072	
Lime	3072	3128	
Lime and Shale	3128	3280	
Lime	3280	3304	
Lime and Shale	3304	3456	Sample
Lime	3456	3812	Top Arbuckle 3806'.

RECEIVED
 FEB 2 1960
 CONSERVATION DIVISION
 Wichita, Kansas