


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County, Sec. 23 Twp. 22 Rge. (E) 14 (W)
Location as "NE/CNWxSWx" or footage from lines 990' fr NL & 330' fr EL of SE/4
Lease Owner Phillips Petroleum Co.
Lease Name Staff Well No. 2
Office Address Box 779 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed January 4 19 51
Application for plugging filed January 14 19 60
Application for plugging approved January 18 19 60
Plugging commenced January 29 19 60
Plugging completed Feb. 2 19 60
Reason for abandonment of well or producing formation Unprofitable to operate

If a producing well is abandoned, date of last production Jan. 19 19 60
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation LKC Depth to top 3443 Bottom 3678 Total Depth of Well PB 3647 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner		3300		8-5/8"	429'	None
Toronto		3320		5-1/2"	3702'	2777'
Brown Lime		3431				
LKC	Oil	3443				
Cong.		3698				
Ch. Viola		3717				
Simp. Shale		3763				
Arb.		3815				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand 3647 to 3430, 5 sx cement to 3395' - shot off & pulled 5 1/2" csg. - mudded hole to 300', rock bridge to 290', 20 sx cement to 230', mudded to 40', rock bridge to 30' and 10 sx cement to surface.

RECEIVED
STATE CORPORATION COMMISSION

FEB 5 1960

CONSERVATION DIVISION
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co.
Address Great Bend, Kans.

STATE OF Kansas, COUNTY OF Barton, ss.
A. J. Willis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. J. Willis
Box 779 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of Feb., 19 60

My commission expires Nov. 18, 1961

Joseph M. Carl
Notary Public.

10
EXPLORATION RECORD

Lease _____ Staff _____

Well 2

Formation Name	Top	Base	Remarks
Sand, red bed	0	410	
Red bed	410	446	
Red bed, sand	446	523	
Red bed, sand, shale	523	957	
Lime & shale	957	1297	
Shale, shells, lime	1297	1640	
Lime & shale	1640	1766	
Lime & Ft. Riley sand	1766	1827	
Lime & shale	1827	1897	
Lime, hard sand	1897	1967	
Lime & shale	1967	2294	
Shale, lime streaks	2294	2378	
Lime, shale	2378	2415	
Shale	2415	2642	
Lime, shale	2642	2725	
Shale	2725	2888	
Lime, shale	2888	3275	
Lime	3275	3293	
Lime, shale	3293	3433	
Lime	3433	3604	
Lime, shale	3604	3645	
Shale, lime streaks	3645	3694	
Lime, shale, chert	3694	3763	
Lime, shale	3763	3825	
Lime	3825	3900	

RECEIVED
STATE CORPORATION COMMISSION

FEB 5 1960

OIL DIVISION
cpc