


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217



Locate well correctly on above
Section Plat

Stafford County, Sec. 4 Twp. 22. Rge. 14 (E) (W) X
Location as "NE/CNW/SW" or footage from lines. NW/SW/SE
Lease Owner Edmiston Oil Company
Lease Name Adams Well No. 1
Office Address 801 First Nat'l. Bldg. Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed June 5, 19 73
Application for plugging approved 19
Plugging commenced June 7, 19 73
Plugging completed June 15, 19 73
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 3845 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	553	-0-
				5 1/2	3788	2734.25'


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Measured T.D. at 3840'. Dumped sand to 3800' and 5 sacks cement. Shot casing at 3310, 3211, 3124, 3003, 2916, 2801 and 2725 ft. Laid down 93 joints of 5 1/2" casing. Squeezed well with 2 sacks hulls, 10 sacks gel and 100 sacks 50/50 pozmix.

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rockhold Engineering, Inc.
Address P. O. Box 698 Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
JAMES W. ROCKHOLD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) James W. Rockhold
Box 698 Great Bend, Ks. 67530 James W. Rockhold
(Address)

19th day of June, 1973

My commission expires Sept. 30, 1975
Cathy Miller Notary Public

DRILLER'S LOG

COMPANY: Edmiston Oil Company
801 First National Bank Building
Wichita, Kansas 67202

ROTARY DRILLING COMMENCED: October 6, 1971

ROTARY DRILLING COMPLETED: October 14, 1971

WELL NAME: #1 ADAMS
NW SW SE Sec. 4-22S-14W
Stafford County, Kansas

CONTRACTOR: E. K. Edmiston Drilling Co., Inc.
801 First National Bank Bldg.
Wichita, Kansas 67202

CASING RECORD: Set 553' of 8-5/8" surface pipe
w/250 sacks cement;
Ran 5 1/2" casing @ 3838'.

L O G

Measurements from top of Kelly Bushing (Elev. 1948 K.B.)

Sand	0 - 40
Sand and Shale	553
Red Bed and Shale	860
Anhydrite	885
Shale and Shells	955
Shale	1710
Lime and Shale	1940
Shale	2170
Lime	2373
Shale w/Lime Streaks	2655
Shale and Lime	3095
Lime w/Shale Streaks	3130
Shale and Lime	3285
Lime	3435
Lime and Shale	3456
Lime	3825
Lime and Shale	3832
Lime	3845 R.T.D.

RECEIVED
STATE CORPORATION COMMISSION
JUN 6 1973
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, E. K. Edmiston, President of E. K. Edmiston Drilling Co., Inc., hereby certifies on behalf of said company, that the above log is a true and correct log of the formations encountered in drilling the above well, as reflected by the daily drilling reports.

E. K. EDMISTON

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

BE IT REMEMBERED that on this 19th day of October, 1971, before me, the undersigned, a Notary Public within and for the County and State aforesaid, came E. K. Edmiston, known to me to be the same person who executed the foregoing instrument on behalf of E. K. Edmiston Drilling Co., Inc., and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My Commission Expires:
November 9, 1973

Marilyn E. Fox, Notary Public

