


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 4 Twp. 22S Rge. 14W (E) (W)
Location as "NE/CNW/SW" or footage from lines N/2 NW SW
Lease Owner Western Petroleum Co., Inc.
Lease Name Unruh Well No. 3
Office Address 925 Patton Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed December 11, 1962 19____
Application for plugging approved December 12, 1962 19____
Plugging commenced December 22, 1962 19____
Plugging completed December 30, 1962 19____
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3867 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	257	none
				5 1/2	none	3019

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in and cleaned out wellar, measured T.D. and moved rods.

Started equipment and dug water pit. Cut off casing head, welded on collar and control head and started working pipe.

Worked pipe and shot @ 3070' - 3005'. Moved pipe 7 ft.

Worked and started pipe. Pu lled pipe.

Pulled pipe and pumped and cleaned cellar and put on swedges. Mixed and pumped 25 sx. mud and 100 sx. cement to squeeze well.

Cleaned pipe and put on pector. Loaded up unit and moved off.

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1963

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 31st day of December, 1962

My commission expires July 23, 1966

Carolyn Herren
Notary Public.



DRILLER'S LOG

COMPANY: HILTON DRILLING COMPANY, INC. LOCATION: C NW SW
 SECTION 4-22-14W
 CONTRACTOR: HILTON DRILLING COMPANY, INC. STAFFORD COUNTY, KANSAS
 FARM NAME: UNRUM No. 3 ELEVATION: 1945 DF
 COMMENCED: JULY 28, 1959 CASING USED: 8 5/8" @ 257' w/ 225 EXD.
 COMPLETED: AUGUST 6, 1959 5 1/2" @ 341' w/ 125 EXD.

CLAY	20
SAND	157
SAND & SHALE	215
SHALE	300
SAND	330
RED BED	860
AMMONITE	890
RED BED, SHALE & SHELLS	1295
SHALE & SHELLS	1670
LINE & SHALE	1800
LINE	2130
SHALE & LINE	2885
LINE	3215
LINE & SHALE	3258
LINE	3357
LINE & SHALE	3450
LINE	3800
LINE & SHALE	3847
TOTAL DEPTH	3847

RECEIVED
 FEB 25 1963
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss.
 COUNTY OF BARTON)

I, THE UNDERSIGNED, BEING DULY SWORN ON OATH, STATE THAT THE ABOVE STATEMENT AND LOG ARE TRUE AND A CORRECT RECORD AND LOG OF THE WELL DRILLED AT THE LOCATION ABOVE DESCRIBED.

HILTON DRILLING COMPANY, INC.

Henry Peacock
 HENRY PEACOCK - LAND DEPARTMENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 7TH DAY OF AUGUST, 1959.

Robert J. ...
 ROBERT J. ...
 Notary Public

MY COMMISSION EXPIRES:
 JANUARY 26, 1963