

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Stafford County, Sec. 4 Twp. 22 Rge. (E) 14 (W)

Location as "NE/CNW&SW" or footage from lines SE NW SE NW

Lease Owner Davis Mud Company

Lease Name Gartung Well No. 5

Office Address Box 366, Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 19

Application for plugging filed July 10 19 72

Application for plugging approved July 11 19 72

Plugging commenced July 14 19 72

Plugging completed July 19 19 72

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation Depth to top Bottom Total Depth of Well 3925 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	445'	8 5/8"	445'	none
		0	3924'	5 1/2"	3924'	2698.43

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded back to 3860' and dumped 5 sacks of cement.

Pumped in 2 sacks of hulls, 15 sacks of mud and 100 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 26 1972  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PIPE PULLERS, INC.

Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON, SS.

Evelyn Roth (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth

Ellinwood, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of July 19 72

My commission expires Feb. 10, 1975

Serge A. Meyer  
Notary Public.

DRILLERS LOG

COMPANY: Aspen Resources, Ltd.  
 CONTRACTOR: Aspen Drilling Co.  
 LEASE NAME: Gartung #5  
 LOCATION: SE-NW-SE-NW Sec. 4-22S-14W  
 Stafford County, Kansas  
 ELEVATION: 1946' K. B.  
 SURFACE CASING: 11 jts. (445') 8 5/8"  
 OIL STRING: 123 jts. (3929') 5 1/2"  
 COMMENCED: April 24, 1970  
 COMPLETED: May 3, 1970  
 ROTARY TOTAL DEPTH: 3925'

<u>FORMATION</u>	<u>DEPTH</u>
Surface clay & Sane	240
Shale	310
Sand	395
Shale	451
Shale & Red Bed	730
Shale & Sand	864
Anhydrite	898
Shale & Shells	1680
Shale & Lime	2165
Lime & Shale	2220
Shale & Shells	2365
Shale	2750
Shale & Lime	3155
Lime & Shale	3315
Lime	3799
Simp. Shale	3853
Arbuckle	3925

Ran 11 jts. (445') 8 5/8" casing set at 451' w/325 sacks cement. Cement did circulate.

DST #1	3770-3799
DST #2	3850-3864
DST #3	3864-3869
DST #4	3852-3872

Ran electric log.

Ran 123 jts. (3929') 5 1/2" casing set at 3924' w/75 sacks cement.

AFFIDAVIT

State of Kansas )  
 ) ss:  
 County of Barton )

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 11 1972  
 CONSERVATION DIVISION  
 Wichita, Kansas

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

*William S. Schachle*  
 William S. Schachle, AFFIANT

Subscribed and sworn to before me this 6th day of May, 1970.

*Theora Holleman*  
 Theora Holleman, Notary Public

My commission expires: April 18, 1972.