

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-083-20,892-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Rine Exploration Inc.

Complete Address Suite 645 300 W. Douglas Wichita Ks.

Lease Name Hastings Well No. 1-32

Location NW-SE Sec. 32 Twp. 22 Rge. 21 (East)(West)

County Hodge man Total Depth 4525

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling Co.

Address Box 176 Chase Ks. 67524 License No. \_\_\_\_\_

Operation Completed: Hour: 2:30 PM Day: 11 Month: 8 Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" S.P. to 371' w/ 275 sx

4 1/2" @ 4522 w/ 150 sx Rec' 3800' of 4 1/2"

Sand bottom Perfs 50' above and 4sx cement on Top.

Plug: 3 sx hulls -> 20 sx gel -> 75 sx cement ->

1 sx hulls -> 10 sx gel -> rel 8 5/8" plug ->

150 sx cement

50/50 Formix 40% gel - 30% cc.

Max pressure 600 # Shut in @ 30 By ALLIED

Amount of Surface Casing: 371'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Steve Plummer  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

On another well in Park Co

RECEIVED  
AUG 15 1982  
CONSERVATION DIVISION  
WICHITA, KANSAS

Signed: S. Plummer  
Conservation Division Agent

INVOICED  
DATE 8-18-82  
INV. NO. 917-W