

Form CP-3
Rev. 6-26-62

14
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1965
2-3-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Martin & Keller *15-185-30012-0000*

Complete Address: 1035 Kennedy Bldg., Tulsa, Oklahoma

Lease Name Parks Well No. # 1

Location SE SE NE Sec. 32 Twp. 23 Rge. 12 (E) (W) W

County Stafford Total Depth 3960'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling Inc.

Address: 912 Central Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 9:00PM Day 1st Month Feb. Year 1965

The Above well was plugged as follows:

317' of 8 5/8" surface pipe, cemented with 250 sacks. Hole was filled
with drilling mud to 250', 1st cementing plug bridged solid with dry
cement and hulls on fluid at 250', and cemented with 25 sacks. Hole
was filled with drilling mud to 40', 2nd cementing plug, bridged solid
with hulls and dry cement on fluid at 40', and cemented with 10 sacks
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 2/3/65
INV. NO. 631-W

Signed: Archie Elving
Well Plugging Supervisor