

Me KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-055-10204-0000

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 27 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Apache Corporation

Complete Address: 823 South Detroit, Tulsa, Okla.

Lease Name Sherman Unit Well No. # 1

Location C SE Sec. 8 Twp. 23 Rge. (E) (W) 31

County Finney Total Depth 2690'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Daco Lease & Well Servicing Co.

Address: Borger, Texas License No. 138

Operation Completed: Hour 9 PM Day 25 Month 3 Year 64

The Above well was plugged as follows:

8 5/8"-343' Circulated w/cement, 4 1/2"-2689' Cemented. Top perforations 2673'

Plug bottom w/10 Sax. cement, top cement 2328' Mud 2328' to 390'

Spotted 35 Sax. cement 390' to 280' Mud 280' to 45'

Plug, 15 Sax. cement 45' to 0 Cut surface off 5' below ground level, weld

cap on surface. Company Pump. Pulled 2243' 4 1/2" pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *J. P. Roberts*
Well Plugging Supervisor

DATE 3/24/64

INV. NO. 8863-u