

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15-055-20,445.0000

Operator's Full Name Challenger Minerals

Complete Address 813. Beacon Bldg. 406. S. Boulder, Tulsa Okla.

Lease Name Bulger Well No. 1

Location C. NW W. Sec. 7 Twp. 23 Rge. 30 (East) (West)

County Finney Total Depth 4970

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Lakin Drilling Co.

Address Lakin, Kans License No. _____

Operation Completed: Hour: 12:00 noon Day: 6 Month: Aug Year: 1981

Plugging Operations attended by Agent? All Part _____ None _____

The above well was plugged as follows:

There was 375' of 8 1/8" surface casing.
Filled with sand to 1260. 1st plug at
1260 with 60 lbs cement. Filled with
mud to 360. Push rubber plug. 2nd plug
at 360' with 35 lbs cement. Filled with
mud to 180. 3rd plug at 180 with 75 lbs
cement. Filled with sand to 40. said
bridge 4th plug at 40-0 with 10 lbs cement
5 lbs cement in rat hole.

I hereby certify that the above well was plugged as herein stated.

Accomplished by
Halliburton

Signed Clarence Thomas
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION
08-07-81
AUG 7 1981
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 9-25-81

INV. NO. 7512 W