



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-185-20417-0000

RECEIVED
STATE CORPORATION COMMISSION

MAY 30 1972

CONSERVATION DIVISION
Wichita, Kansas

6-30-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cameron of H-30 Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: Parrish Oil Co.

Complete Address: 714 4th Natl Bldg. Wichita, Ks

Lease Name: Fischer Well No. 1

Location: SW/NE/SW Sec. 30 Twp. 23s Rge. 12 (E)(W) W

County: Stafford Total Depth 3725 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Cameron was instructed to plug the well as follows:

278 ft 8 5/8 surface pipe cemented with 225 sacks. Pump
40 sacks cement to 600 ft. 2nd plug at 300 ft with 25
sacks cement. Mud to 40 ft, plug, 1/2 sack hulls, 15 sacks
cement to surface. 2 sacks cement in rat hole.

Pumped by Halliburton Cementing Co. Great Bend, Ks

Very truly yours,

Conservation Division Agent