



JOHN ANDERSON, Jr. Governor
WILLIAM L MITCHELL Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-185 30012-0000

RECEIVED
STATE CORPORATION COMMISSION

FEB 3 1965
2-3-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Cal Roberts of Leben Drilling Inc. has this
date requested permission to plug the following described well:

Mr. Roberts guarantees payment of the plugging fee.

Operator's full Name: Martin & Keller

Complete Address: 1035 Kennedy Bldg., Tulsa, Oklahoma

Lease Name: Parks Well No. # 1

Location: SE SE NE Sec. 32 Twp. 23 Rge. 12 (E) (W) W

County Stafford Total Depth 3960 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Roberts was instructed to plug the well as follows:

317' of 8 5/8" surface pipe, cemented with 250 sacks. Fill
hole with drilling mud to 250', 1st cementing plug, bridge
with hulls and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent