



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

15-185-19388-0000

RECEIVED  
STATE CORPORATION COMMISSION

MAR 4 1963

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Feb. 27, 1963.

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Earl Quattlebaum of National Drilling Co. has this date requested permission to plug the following described well:

Mr. Earl Quattlebaum guarantees payment of the plugging fee.

Operator's full Name: National Drilling Co.

Complete Address: 531 Petroleum Bldg, Wichita, Kans.

Lease Name: Hartnett #2 Well No. #2

Location: SW-NE SE Sec. 34 Twp. 23 Rge. 12 (E) (W) X

County Stafford County Total Depth 3880' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Earl Quattlebaum was instructed to plug the well as follows:

~~200' of 8 5/8" surface pipe circulated with cement. Hole filled to 180' with heavy drill mud, 1/4 sack hulls, 1st cem. plug & 20 sacks cement through drill pipe. Hole filled to 40' with heavy drill mud, 1/4 sack hulls, 2nd cem. plug, & 10 sacks cement to base of cellar. Rathole bridged and 2 sacks cement.~~

Very truly yours,

*Herman J. Justus*  
 Conservation Division Agent