


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kiowa County, Sec. 7 Twp. 28S Rge. 16W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines \_\_\_\_\_  
C-NW NE  
Lease Owner Lifestyle Energy Corp.  
Lease Name C. Mahoney Well No. 1  
Office Address 100 N. Central Expressway-Suite 809,  
Character of Well (Completed as Oil, Gas or Dry Hole) Richardson, TX 75080  
Dry Hole  
Date Well completed January 9, 1981  
Application for plugging filed Verbal Application 19  
Application for plugging approved Verbal Approval 19  
Plugging commenced January 9, 1981  
Plugging completed January 9, 1981  
Reason for abandonment of well or producing formation \_\_\_\_\_



If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,758'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	280'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,758 ft. (rotary total depth) to 550 ft. Set plug at 550 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 550 ft. to 350 ft. Set plug at 350 ft. and cemented with 35 sacks cement. Filled hole with heavy rotary mud from 350 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole and 5 sacks cement in mouse hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.  
Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Dean Britting, Agent ~~XXXXXX~~ of owner) ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
251 N. Water - Suite 10, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of January, 19 81

Elsie Willison  
Elsie Willison - Notary Public.

My commission expires July 25, 1982

1-23-81  
JAN 23 1981  
CONSERVATION DIVISION  
Wichita, Kansas

KANSAS DRILLERS LOG

COMPANY Lifestyle Energy Corp.

SEC. 7 T. 28S R. 16W

FARM C. Mahoney NO. 1

LOC. C-NW NE

COUNTY Kiowa

ROTARY TOTAL DEPTH 4,758'

COMM. January 2, 1981

COMP. January 9, 1981

CONTRACTOR H-30, INC. (Rig #77)

ISSUED January 16, 1981

CASING

10 3/4"

8 5/8" Set at 280' cemented w/225 sxs cement

ELEVATION 2,158' K.B

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Anhydrite	290'
Red Bed and Sand	2,110'
Shale and Lime	2,290'
Lime and Shale	2,500'
Shale	2,768'
Lime and Shale	4,758'
Rotary Total Depth	4,758'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
 \_\_\_\_\_  
 Dean Britting

State of Kansas        )  
                           ) ss:  
 County of Sedgwick )

Subscribed and Sworn to before me a Notary Public in and for said county and state this 16th day of January, 1981.

*Elsie Willison*  
 \_\_\_\_\_  
 Elsie Willison - Notary Public

My Commission Expires:  
 July 25, 1982