


Give All Information Completely  
Make Required Affidavit  
Cash or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 27 Twp. 22S Rge. 14 (W)



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines NW SW SW  
Lease Owner Halliburton Oil Producing Company  
Lease Name Krankenber Well No. 2  
Office Address 520 Cameron Bldg, Oklahoma City, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed 10-20-62 19\_\_  
Application for plugging filed 10-20-62 19\_\_  
Application for plugging approved 10-20-62 19\_\_  
Plugging commenced 10-20-62 19\_\_  
Plugging completed 10-20-62 19\_\_  
Reason for abandonment of well or producing formation non-productive

If a producing well is abandoned, date of last production - 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp  
Producing formation - Depth to top - Bottom - Total Depth of Well 3706 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	260'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from - feet to - feet for each plug set.

Filled hole with heavy mud, set 20 sacks at 220',  
10 sacks at 35' to top, 2 sacks in rat hole.

11-12-62

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 1 1962  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Christie-Stewart Drilling Company  
Address 611 Union Center

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Robert C. Lewellyn (employee of owner) or (~~XXXXXX~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) [Signature]  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 9th day of November, 19 62

Patricia Hotman

Notary Public.

My commission expires January 19, 1964



## WELL LOG

Company: Halliburton Oil Producing Company      Sec.: 27-22S-12W  
 Farm: Krankenberg No. 2      Loc: NW SW SW  
 Rig No. 1      County: Stafford  
 Total Depth 3706      State: Kansas  
 Comm: 10-8-62      Comp: 10-20-62  
 Contractor: Christie-Stewart Drilling Company  
 Casing: 8 5/8ths" @ 260' KBM/200sx      Elevation: 1850 KB  
 Production: D & A

247'	Surface soils, clays, bkn sd & sh.	2708'	Broken Limestone
621'	Broken sd, sh & ls	2745'	Shale
642'	Anhydrite	2800'	Limestone
1103'	Broken sd & sh	2840'	Shale
1525'	Sd, few sh & ls strks	3133	finely crystalline ls, broken
1650'	Bkn Limestone		
1700'	Bkn sand, wtr	3138'	Black shale
1770'	Shale, gray	3168'	Broken limestone
1903'	Limestone	3264'	Shale, gray
2190'	Broken shale & Limestone	3425'	Broken limestone & sn
2220'	Shale	3440'	Limestone, show oil
2305'	Broken limestone	3443'	Shale
2400'	Shaley limestone	3482'	Bkn Ls, show oil
2500'	Broken limestone, tr. sand	3486'	Shale
2530'	Shale	3520'	Limestone, show oil
2555	Limestone	3556'	Broken limestone
2593	Shale	3590'	Shale
		3667'	Cherty lime, show oil
		3702'	Bkn sd & sh
		3706'	Dolomite
		3706'	Total depth

## FORMATION TOPS

Formation	Depth	Datum
Heebner	3132'	-1282
Brown lime	3264	-1414
Lansing	3290	-1440
Base Kansas City	3517	-1667
Viola	3590	-1740
Simpson	3688	-1838
Arbuckle	3702	-1852
Total Depth	3706	-1856

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 NOV 19 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

## DRILL STEM TESTS

DST #1 3421-42 - 1 hr. Weak blow; rec. 70' socm; 1BHP 532# - 30; IFP 20# FFP 48# FSIP 103# - 30	DST No. 2 3438-3500 - 1 hr. Weak blow, Rec. 85' SOCM; 1BHP 786 - 30; IFP 20# FFP 46# FSIP 130# - 30
DST #3 3595-3617 (Straddle) 1 hr; very weak blow; rec. 60' mud, few oil spks. 1BHP 300# - 30 IFP 20# FFP 40# FSIP 90# - 30	

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.

Robert C. Lewellyn, employee of owner of the above described well, first being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

Robert C. Lewellyn

Subscribed and Sworn to before me this 9th day of November, 1962.

My commission expires January 19, 1962

Patricia Holmes

Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 12 1962  
CONSERVATION DIVISION  
Wichita, Kansas