

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail & Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 23 Twp. 22 Rge. 12 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NE SW SE

Lease Owner B. E. Ash

Lease Name Byars Well No. B-1

Office Address _____

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed May 31 19 59

Application for plugging filed May 31 19 59

Application for plugging approved May 31 19 59

Plugging commenced May 31 19 59

Plugging completed May 31 19 59

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3688 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	276'	8 5/8"	276'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug 240'. Plugged with hulls and 20 sacks cement. Top plug at 35' with hulls and 10 sacks cement. Completed May 31, 1959

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bea Drilling Company
Address Box 206 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Jean Kimber (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jean Kimber
Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of June, 19 59

My commission expires April 27, 1961

Virgil E. Broadfoot
Notary Public.

PLUGGING
FILE SEC. 23 T. 22 R. 12 W
BOOK PAGE 57 LINE 1

B. E. ASH
Box 206
Ellinwood, Kansas

Well Log

Byars B-1

NE SW NE

23-22-12W

Stafford County, Kansas

Elevation: 1851' DF

		Formation Tops	
0-150	Clay & Sand		
150-620	Red Bed		
620-650	Andhydrate	Heebner	3144-1290
650-1040	Shale	Toronto	3161-1306
1040-1445	Salt & Shale	Brown Lime	3273-1419
1445-1665	Shale & Shells	Lansing Kansas City	3298-1444
1665-2910	Shale & Lime	Viola	3581-1727
2910-2980	Lime	Simpson	3620-1766
2980-3065	Lime & Shale	Arbuckle	3677-1823
3065-3300	Lime	RTD	3688-1834
3300-3340	Shale & Lime		
3340-3655	Lime		
3655-3688	Conglomerate		

DST # 1 3300-3340 open 1 hour, recovered 10 feet of mud. No shows of oil. 30 minute IBHP 75#, 20 minute FBHB 30#, IFP 12#, FFP 25#.

Plugged and abandoned, May 31, 1959

State of Kansas
County of Barton

Richard P. Crimond employee of owner, of the above described well, being first duly sworn on oath says: " That I, have knowledge of the facts, statements, and matters, herein contained and the log of the above described well as filed and that the same are true and correct.

Richard P. Crimond

Subscribed to and sworn to before me this 25th day of June, 1959.

Walter H. [Signature]
Notary Public

April 27, 1961
My Commission Expires

RECEIVED
STATE CONSERVATION COMMISSION

AUG 20 1959

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 23 T. 22 R. 12W
BOOK PAGE 57 LINE 1