


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Flat

Stafford County, Sec. 23 Twp. 22 Rge. 12 (W)
Location as "NE/CNW/SW" or footage from lines C S/2 NE NE
Lease Owner Santa-Fe Pipe & Supply, Inc.,
Lease Name Byers Well No. 3
Office Address Box 562, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed July 22 19 58
Application for plugging filed May 8 19 67
Application for plugging approved May 9 19 67
Plugging commenced May 8 19 67
Plugging completed May 16 19 67
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 3661' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	285'	none
				5-1/2"	3656'	2962.75

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3661-3275' - sand
3275-3235' - 5 sacks cement
3235- 270' - mud
270-255' - rock bridge
255-249' - 2 sacks cement with calcium chloride
249-180' - 23 sacks cement
180-40' - mud
40 - 30' - rock bridge
30 - base - 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1967
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Santa Fe Pipe & Supply, Inc.,
Address P. O. Box 562, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
T. L. Nutt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt
Box 562, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of May, 19 67

My commission expires July 31, 1970

Mary M. Guenier
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

MAY 29 1967

CONSERVATION DIVISION
Wichita, Kansas

Well Log

Byer "A" 3

C S/2 NE NE 23-22-12W
Stafford County
Kansas

Date Staked: 6/29/58
Rig Up Rotary: 6/30/58
Set Surface: 7/2/58
Set Oil string: 7/16/58
Completed: 7/22/58
Started Pump: 8/2/58

Elevation: KB 1861' DF 1858'

Formation Tops:
12
Heebner 3138-2277
Brown lime 3269-1408
Lansing-KC 3294-1433
Viola 3551-1690
Simpson 3605-1744
Sand 3627-1766
Arbuckle 3654-1793
Rot. TD 3657-1796

Casing Record:
285' 8/5/8" cemented w/165 sax.
3656' 5 1/2" cemented w/100 sax,
poznix.

Log (Meas. to bottom of form.) Completion

140	sand & clay	7-19	Rigged up cable tools. Swab hole
280	red bed	down.	
615	red bed & shale	7-20	Drilled plug, float, cement & shoe
640	anhydrite	Bailed clean. Tested. Swabbed hole down to	
1250	shale & shells	100' of bottom. 19 bbl.	
1450	shale, salt & shells	7-21	Swabbed. Drilled 1' new hole. Test.
1670	sandy lime & shale	3 bbl. per hr. 30% water.	
1735	sandy lime	7-22	110' fluid in hole. 350' oil and
2900	shale & lime	750' water. Rigging down cable tools.	
3105	Lime & shale		
3657	lime		
3657	Rotary total depth.		

STATE OF KANSAS

COUNTY OF BARTON SS:

C. F. Krehbiel

~~XXXXXXXXXX~~, ~~XXXXXX~~ ^{inc.} of Bea Drilling Company, being first
duly sworn on oath says: I have knowledge of the facts, statements,
and matters herein contained and the log of the above well as filed
and that the same are true and correct.

C. F. Krehbiel

~~XXXXXXXXXX~~
C. F. Krehbiel, Vice-Pres.
Bea Drilling Co., Inc.

Subscribed and sworn before me this 27th day of May 1967

Mary M. Guesnier
Notary Public

My commission expires: 7-31-70
7-31-70
