

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 23 Twp. 22S Rge. 12W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

NE NE NW

Lease Owner Petroleum Energy, Inc.
Lease Name BYER Well No. 1
Office Address 710 One Twenty Bldg., Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole


Date Well completed 5/12 1981
Application for plugging filed 5/12 1981
Application for plugging approved 5/12 1981
Plugging commenced 5/12 1981
Plugging completed 5/12 1981

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3677
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	309'	8-5/8"	309'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

120 sks 50/50 poz., 2% gel, 3% cc.:

60 sks @ 600'

40 sks @ 300'

10 sks @ 40'

10 sks in rathole

Plug down 1:00 PM, 5/12/81

5-19-81

RECEIVED

STATE CORPORATION COMMISSION

MAY 19 1981

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet) Wichita, Kansas

Name of Plugging Contractor Allen Drilling Company
P.O. Box 1389, Great Bend, KS 67530

STATE OF KANSAS COUNTY OF BARTON, ss.
Greg Davidson (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Greg Davidson
P.O. Box 1389, Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of May, 19 81



Ruth Brack
Notary Public.

My commission expires _____

DRILLER'S WELL LOG

DATE COMMENCED: 05/06/81
 DATE COMPLETED: 05/12/81

Petroleum Energy, Inc.
 BYER No. 1
 NE NE NW
 Sec. 23, Twp. 22S, Rge. 12W
 Stafford County, Kansas

ELEVATION: 1865' G.L.
 1870' K.B.

FORMATION DATA:

3162 - 3290' Shale
 3290 - 3310' Lime, shale
 3310 - 3567' Lime
 3567 - 3618' Chert
 3618 - 3658' Sand
 3658 - 3677' Dolomite
 3677' RTD

Heebner 3162'
 B Lime 3290'
 Lansing 3310'
 Viola 3567'
 SimpsonSand 3618'
 Arbuckle 3658'
 RTD 3677'

RECEIVED
 STATE CORPORATION COMMISSION

MAY 19 1981
 CONSERVATION DIVISION
 Wichita, Kansas

SURFACE DATA:

Ran 7 jts. new 20# 8-5/8" casing, tally: 302'; Set @ 309' w/ 225 sks 60/40 poz., 2% gel, 3% c.c. cement. circ., plug down 8:15 PM, 5/6/81 By Sun

PLUGGING DATA:

120 sks 50/50 poz., 2% gel 3% cc.:
 60 sks @ 600'
 40 sks @ 300'
 10 sks @ 40'
 10 sks in rathole
 Plug down 1:00 P.M., 5/12/81 By Sun

A F F I D A V I T

STATE OF KANSAS)
 COUNTY OF BARTON) ss.

Greg Davidson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Greg Davidson

Subscribed and Sworn to before me this 15 day of May, 1981.



Ruth Brack
 Notary Public