

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
806 Bittling Building
Wichita, Kansas

Stafford

County. Sec. 23 Twp. 22 Rge. 12 (E) (W)

Location as "NE/CNW%SW%" or footage from lines SE NW NW

Lease Owner Wunderlich - Inger

Lease Name Lat - Byers

Well No. 4

Office Address Box 39 Chase, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed March 8 19 56

Application for plugging filed March 8 19 56

Application for plugging approved March 8 19 56

Plugging commenced March 8 19 56

Plugging completed March 8 19 56

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage

Producing formation Depth to top Bottom Total Depth of Well 3801 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface pipe		-0-	224	8 5/8	224	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole to 220' with rotary mud.
Dumped 13 sacks hulls
Pushed plug to 220'
Poured 20 sacks cement through drill pipe on plug
Filled hole to 35'
Put in 1/3 sack hulls and top plug with
2 wires and 10 sacks cement on top

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor A. L. Jackson Drilling Company
Address Box 194 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
A. L. Jackson (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. L. Jackson
Box 194 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of March, 19 56

My commission expires April 27, 1957

Notary Public.

PLUGGING
FILE SEC 23 T 22 R 12 W
BOOK PAGE 44 LINE 44

3-20-86

Well Log
 Lat-Byers #4.
 SE NW NW 23-22-12
 Stafford County, Kansas

0 - 45	Top soil - sand
45 - 200	Sand - shale - shells
200 - 224	Red bed
224 - 420	Red bed and shale
420 - 985	Red bed and shells
985 - 1010	Anhydrite
1010 - 1420	Shale and shells
1420 - 1440	Sand and shale
1440 - 1520	Shale and shells
1520 - 1855	Lime and shale
1855 - 1875	Sand - lime - shale
1875 - 2450	Lime and shale
2450 - 2585	Shale and shells
2585 - 2790	Shale and lime
2790 - 2840	Lime and shale
2840 - 3070	Lime
3070 - 3145	Lime and shale
3145 - 3230	Lime
3230 - 3295	Lime - shale - doug.
3295 - 3308	Lime and shale
3308 - 3560	Lime
3560 - 3582	Lime and shale
3582 - 3592	Marn. shale and lime
3592 - 3619	Viola
3619 - 3640	Viola (chert)
3640 - 3649	Cherty lime
3649 - 3655	Shale
3655 - 3708	Simp. shale and sandy shale
3708 - 3755	Lime
3775 - 3801	Lime and shale
3801	T. D.

STATE OF KANSAS

COUNTY OF BARTON ss


A. L. Jackson, owner of A. L. Jackson Drilling Company, being first duly sworn on oath says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct.

A. L. Jackson
 A. L. Jackson

Subscribed and sworn before me this 10th day of March, 1956

Virgil E. Esiford, Jr.
 Virgil E. Esiford, Jr.
 Notary Public Barton County

My Commission expires April 27, 1957



FILED
 MARCH 10 1956
 BARTON COUNTY
 VIRGIL E. ESIFORD, JR.
 NOTARY PUBLIC