


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

*Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County, Sec. 23 Twp. 22 Rge. (X) 20 (W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines SW SW SE/4
Lease Owner W. B. ARMER
Lease Name Anderson Well No. 1
Office Address 711 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed October 21, 19 59
Application for plugging filed October 21, 19 59
Application for plugging approved October 21, 19 59
Plugging commenced October 21, 19 59
Plugging completed October 22, 19 59
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4445 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	262	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

CEMENTED BY HALLIBURTON. SQUEEZED WITH 90 SACKS POZMIX.
PUMPED PLUG TO 134 FEET. THE NEXT MORNING THIS PLUG WAS
CHECKED AND IT WAS STILL THERE. FILLED HOLE WITH HEAVY MUD
TO 35 FT., SET PLUG AT 35 FEET, CEMENTED WITH ONE THIRD SACK
OF HULLS AND 10 SACKS CEMENT TO BOTTOM OF THE CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor ARMER, INC.
Address 709 PETROLEUM BLDG. WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

L. C. Sponenberg (employee of owner or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg

SUBSCRIBED AND SWORN TO before me this 28th day of October, 19 59

My commission expires February 13, 1960

(Address)
Rose Furey
Rose Furey Notary Public.



KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY M. B. Armer

SEC. 23 T. 22 R. 20
LOC. SW SW SW

FARM Anderson


NO. 1

TOTAL DEPTH 4445
COMM. 10/8/59

COMP. 10/22/59

COUNTY Pawnee
KANSAS

SHOT OR TREATED
CONTRACTOR Armer, Inc.
ISSUED



CASING	
20	10
15	8 262'
12	6
13	5

ELEVATION 2166 G. L.

PRODUCTION D+A

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	40'
Shale, Sand & Shells	262
Shale, Shells & Red Bed	633
Gyp	700
Shale & Gyp	735
Sand	855
Sand, Shale & Shells	890
Shale & Shells	1530
Shale, Shells & Lime	1865
Shale & Shells	2080
Shale & Lime	2530
Lime	2625
Lime & Shale	3680
Lime	3965
Lime & Shale	4170
Lime	4280
Lime & Shale	4385
Lime	4425
Cherty Lime	4445

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1959
CONSERVATION DIVISION
Wichita, Kansas

Formation Tops:

	Sample Tops		Electric Log Tops
Heebner	3745 -1574		3734 -1563
Toronto	3762 -1591		3753 -1582
Brown Line	3814 -1643		3814 -1643
Lansing	3829 -1658		3825 -1654
Basil Pennsylvanian Conglomerate			4385 -2214
Mississippian			4408 -2237
Rotary Total Depth	4445		4444

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

ARMER, INC.

By L. C. Sporenberg
L. C. Sporenberg

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, in and for said County and State, this 28th day of October, 1959.

Rose Furey
Rose Furey, Notary Public

My Commission Expires February 13, 1960.