

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Pawnee County, Sec. 21 Twp. 22 Rge. (E) 20 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NE NE/4

Lease Owner M. B. Armer

Lease Name Smith Well No. 1

Office Address 710 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed April 7, 1953

Application for plugging filed April 7, 1953

Application for plugging approved April 7, 1953

Plugging commenced April 7, 1953

Plugging completed April 7, 1953

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4756 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	242'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy Rotary Mud from 4756 ft.

to 240 ft. set plug and 20 sacks cement through

drill pipe. Filled with mud to 35 ft. set plug

and ran 10 sacks cement at the surface.

RECEIVED
STATE CORPORATION COMMISSION
APR 16 1953
CONSERVATION DIVISION
Wichita, Kansas

4-16-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor M. B. Armer

Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

L. C. Sponenberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg

(Address)

SUBSCRIBED AND SWORN to before me this 13th day of April, 1953

Lorraine M. Johnson
Notary Public.

My commission expires Oct. 13, 1956.

PLUGGING
FILE SEC 91 T 22 R 20W
BOOK PAGE 91 LINE 39

L O G

Company: M. B. Armer
 Contractor: M. B. Armer (Unit Rig)
 Drilling Commenced: 3/21/53
 Drilling Completed: 4/8/53
 Elevation: 2226 K.B.
 2223 D.F.
 2221 Gr.

Farm: Smith #1
 Location: C/NW NE NE Sec. 21-22S-20W
 Pawnee County, Kansas
 Casing Record: 8 5/8" casing at 242'
 with 125 sacks cement.

(figures below indicate bottoms)

Surface Clay & Sand	40
Shale & Shells	170
Shale, Shells & Sand streaks	240
Red Bed	242
Blue Shale	500
Red Bed, Shale & Shells	800
Sand	925
Shale & Sand Streaks	1000
Shale & Shells	1040
Shale, Shells & Red Bed	1365
Anhydrite	1390
Shale & Shells	1910
Shale & Lime	3930
Lime	3965
Shale & Lime	4010
Lime	4080
Shale & Lime	4143
Lime	4185
Shale & Lime	4315
Cherty Congl.	4518
Cherty Lime	4545
Chert & Lime	4561
Cherty Lime, Shale & Sand	4619
Cherty Lime Hard	4685
Lime	4724
Cherty Lime	4756
R.T.D.	4756

FORMATION TOPS (R.B. Meas.)

LANSING	3918	(-1692)
CONGLOMERATE	4143	(-2205)
MISSISSIPPI	4488	(-2262)
KINDERHOOK	4544	(-2318)
VIOLA	4645	(-2419)
R.T.D.	4756	(-2530)

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

By *C. L. Spruisky*

STATE OF KANSAS }
 } SS:
 COUNTY OF SEDGWICK }

Subscribed and sworn to before me, a notary public, in and for said County and State this 14th day of April, 1952.

Syrraine M. Johnson
 Notary Public

My Commission Expires: Oct. 13, 1956.

PLUGGING
 FILE SEC 21 T 22 R 20 W
 BOOK PAGE 91 LINE 39

RECEIVED
 STATE CORPORATION COMMISSION
 APR 16 1953
 CONSERVATION DIVISION
 Wichita, Kansas