

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-21,204-0000

LEASE NAME Smith

WELL NUMBER #1

SPOT LOCATION NW NE

SEC. 6 TWP. 22 RGE. 20 (E) (W)

COUNTY Pawnee

Date Well Completed 7-16-85
2:00 PM,

Plugging Commenced 7-16-85

3:40 PM,
Plugging Completed 7-16-85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Zenith Drilling Corporation

ADDRESS 505 Fourth Financial Center
Wichita, Kansas 67202

PHONE # (316) 265-6697 OPERATORS LICENSE NO. 5141

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District No. 1

Is ACO-1 filed? If not, is well log attached? Yes

Producing formation Depth to top bottom T.D. 4462'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	388'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Filled hole with heavy mud plugged through open ended drill pipe. Plugged 50 sacks at 1360'; 70 sacks at 840'; 40 sacks at 420'; 1/2 sack hulls, plug and 10 sacks at 40'; 15 sacks in rathole, 10 sacks in mouse hole. Used 60/40 Pozmix plug 4% gel (total 6%) and 3% cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142
Address P. O. Box 129
Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me **RECEIVED**

STATE CORPORATION COMMISSION

7-22-85
FILE 22

STERLING DRILLING COMPANY
(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
(Address) P. O. Box 129, Sterling, Ks.
67579

SUBSCRIBED AND SWORN TO before me this 17 day of July, 19 85
Wichita, Kansas

Agnes D. Wurst
Agnes D. Wurst, Notary Public

My Commission expires: 4-6-89



STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - SMITH #1

Located: NW NE, Section 6-22S-20W, Pawnee County, Kansas

OWNER: Zenith Drilling Corporation

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 8, 1985

COMPLETED: July 16, 1985

TOTAL DEPTH: 4462'

LOG

0 - 391 Soil and Shale
 391 - 910 Shale
 910 - 1338 Shale and Sand
 1338 - 1353 Anhydrite
 1353 - 1362 Shale
 1362 - 4350 Lime and Shale
 4350 - 4422 Lime and Shale, Chert
 4422 - 4437 Mississippian
 4437 - 4462 Lime and Shale

CASING RECORD

Ran 9 joints new 8 5/8", 20# casing.
 375.67' pipe set at 388' K.B.
 Cemented with 250 sacks 60/40 Pozmix
 plus 3% cc. Plug down at 2:00 AM,
 7-9-85, by Howco.

Plugged.

Deviation Surveys: 1° at 1637'
 3/4° at 4422'

RECEIVED
 STATE CORPORATION COMMISSION

7-22-1985

CONSERVATION DIVISION
 Wichita, Kansas