

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Hodgeman County, Sec. 35 Twp. 22S Rge. (E) 21 (W)
Location as "NE/CNW%SW%" or footage from lines C NW SW
Lease Owner Clinton Oil Company
Lease Name V. DITUS "A" Well No. 1
Office Address 6810 West Hi-Way 54, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 3, 19 69
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced May 3, 19 69
Plugging completed May 3, 19 69
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Edgar Eves of Sublette)

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4565 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	338'	8-5/8"		-----
	Casing					

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1969
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud from Total Depth to 800 Feet;
Plug and 30 sax cement; Mud to 350
Feet; Plug and 30 sax cement; Mud
to 40 Feet; Plug and 15 sax cement
to Base of Cellar; 2 sax cement in
Rat Hole. Job completed @ 5 A.M.
on 5/3/69.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Bldg., Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Wayne W. Kahmeyer of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer
500 Bitting Building, Wichita, Kansas
(Address)

Louise K. Whitted
Louise K. Whitted - Notary Public.



SUBSCRIBED AND SWORN to before me this 6th day of May, 19 69
November 26, 1970

DRILLERS LOGV. DITUS "A" NO. 1

CASING RECORD:	OPERATOR: Clinton Oil Company	DESCRIPTION:
8-5/8" @ 338' w/200 sax cement	CONTRACTOR: Sage Drilling Co.	C NW SW Sec. 35-22S-21W Hodgeman Co., Kansas
TOTAL DEPTH: 4565'	COMMENCED: April 22, 1969	ELEVATION: 2297KB
	COMPLETED: May 3, 1969	


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	40	
Shale	40	338	
Shale, Shells & Red Bed	338	780	
Shale & Shells	780	855	
Sand	855	1010	
Shale & Shells	1010	1410	
Anhydrite	1410	1469	
Shale & Shells	1469	1885	
Shale & Lime	1885	2288	
Lime	2288	2489	
Lime & Shale	2489	2619	
Lime	2619	2780	
Lime & Shale	2780	3150	
Lime	3150	3400	
Lime & Shale	3400	3752	
Lime & Chalky Shale	3752	3860	
Lime	3860	4545	
Mississippi Lime & Chert	4545	4555	
Mississippi Lime	4555	4565	D&A

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1969
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer
Wayne W. Kahmeyer



Subscribed and sworn to before me this 6th day of May, 1969.

Louise K. Whitted
Louise K. Whitted - Notary Public

My commission expires:
November 26, 1970.