

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 32 TWP. 22S RGE. 21W E/W
Location as in quarters or footage from lines:
NW SE

Locate Well
correctly on above
Section Platt.

Lease Owner Rine Exploration Company
Lease Name Hasting 1-32 Well No. _____
Office Address Suite 645 300 W. Douglas Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 8-4-82
Plugging completed 8-11-82
Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation _____ Depth to top _____ bottom _____ T.D. 4525'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	371'	none
				4-1/2"	4522'	3803'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with sand to 4450' and ran 4 sacks cement. Shot casing @3920',
3800', pulled a total of 94 joints of 4-1/2" casing. Plugged well with 3 sacks hulls,
20 sacks gel, 75 sacks cement, 1 sack hulls, 10 sacks gel, released plug and displaced
with 150 sacks cement.

Plugging complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that ~~the same~~ are true and correct. So help me God.

STATE CORPORATION COMMISSION

AUG 19 1982

(Signature) R. Darrell Kelso
Box 347 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 82

My Commission expires:



[Signature]
Notary Public.

DRILLERS LOG

OPERATOR: Rine Exploration Company
645 R. H. Garvey Building
Wichita, Kansas 67202

WELL NAME: ~~Hastings #1-32~~
App. NW SE
Sec. 32-22S-21W
Hodgeman County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: 9/4/81

COMPLETED: 9/11/81

RTD: 4525'

SURFACE CASING: 8-5/8" set at 371' with 275 sx cement

PRODUCTION CASING: 4-1/2" set at 4522' with 150 sx cement

0' to 380' 12 1/4" Surface Hole
380' to 1403' Shale
1403' to 1440' Anhydrite
1440' to 2010' Shale & Shells
2010' to 2630' Shale
2630' to 3349' Shale & Lime
3349' to 3517' Shale
3517' to 3792' Lime
3792' to 4005' Shale & Lime
4005' to 4210' Lime & Shale
4210' to 4525' Lime
RTD 4525'

STATE OF KANSAS

COUNTY OF SEDGWICK


I, James C. Remsberg, of the Slawson Drilling Company, Inc.
hereby state the above is an accurate copy of the Hastings #1-32 log for
Rine Exploration Company.

James C. Remsberg
James C. Remsberg

Subscribed and sworn to me
this 21st day of September, 1981

Mary Lou Taylor
Mary Lou Taylor, Notary

My commission expires January 17, 1985



RECEIVED
STATE CORPORATION COMMISSION
APR - 5 1982
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

OPERATOR: Rine Exploration Company
645 R. H. Garvey Building
Wichita, Kansas 67202

WELL NAME: XXXXXXXXXXXXXXXXXXXX *HASTINGS #1-32*
App. NW SE
Sec.32-22S-21W
Hodgeman County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: 9/4/81

COMPLETED: 9/11/81

RTD: 4525'

SURFACE CASING: 8-5/8" set at 371' with 275 sx cement

PRODUCTION CASING: 4-1/2" set at 4522' with 150 sx cement

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1982
CONSERVATION DIVISION
Wichita, Kansas

0' to 380' 12 1/4" Surface Hole
380' to 1403' Shale
1403' to 1440' Anhydrite
1440' to 2010' Shale & Shells
2010' to 2630' Shale
2630' to 3349' Shale & Lime
3349' to 3517' Shale
3517' to 3792' Lime
3792' to 4005' Shale & Lime
4005' to 4210' Lime & Shale
4210' to 4525' Lime
RTD 4525'

STATE OF KANSAS

COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.
hereby state the above is an accurate copy of the Hastings #1-32 log for
Rine Exploration Company.

James C. Remsberg
James C. Remsberg

Subscribed and sworn to me
this 21st day of September, 1981

Mary Lou Taylor
Mary Lou Taylor, Notary

My commission expires January 17, 1985

