

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-185-21848-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Stafford SEC. 30 TWP. 23S RGE. 12 NW
 Location as in quarters or footage from lines:
660' FNL; 660' FEL, NE NE

Lease Owner Zenith Drilling Corporation
 Lease Name Curtis #1 Well No. 1
 Office Address Suite 505, Fourth Financial Center, Wichita, Ks 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 9-16-83
 Application for plugging filed 9-16-83
 Plugging commenced 7:00 AM, 9-16-83
 Plugging completed 8:30 AM, 9-16-83
 Reason for abandonment of well or producing formation Dry Hole

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bud Metz

Producing formation _____ Depth to top _____ bottom _____ T.D. 3635'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	295'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Filled hole with heavy mud.
50 sacks 60/40 Pozmix with 2% gel and 3% cc
at 720'; 50 sacks at 340'; solid bridge and 10 sacks
at 40'. 16 sacks in rathole and 5 sacks in water well.

SEP 21 1983
 1983
 1983

9-21-83

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY
 (Signature) [Signature]
F. A. Wuellner, Secretary
 (Address)
P. O. Box 129, Sterling, Kansas
67579

SUBSCRIBED AND SWORN TO before me this 19th day of September, 19 83.



[Signature]
 Agnes D. Wurst, Notary Public.

My Commission expires: 4-6-85

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

15-195-21848-0000

WELL LOG - - - - - CURTIS #1
Located: C NE NE, Section 30-23S-12W, Stafford County, Kansas

OWNER: Zenith Drilling Corporation
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: September 10, 1983
COMPLETED: September 16, 1983

TOTAL DEPTH: 3635'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 95 Sand and Gravel	Ran 7 joints 8 5/8" casing. 282.36'
95 - 715 Shale	pipe set at 295' K.B. Cemented with
715 - 735 Anhydrite	250 sacks 60/40 Pozmix, 2% gel and
735 - 1180 Shale	3% cc. Plug down at 3:30 PM, 9-10-83,
1180 - 3610 Lime and Shale	by Howco.
3610 - 3635 Lime	Plugged.

Deviation Surveys: 1° at 1722'
1° at 3635'

RECEIVED
STATE COMMISSION
SEP 21 1983
CONSERVATION DIVISION
Wichita, Kansas