

**Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas**

## 03

**Strike out upper line when reporting plugging off formations.**

NORTH

Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production.....19.....  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced?.....Yes.....

Name of Conservation Agent who supervised plugging of this well Mr. Stough  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3962 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

### CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to .....feet for each plug set.

|                     |                  |
|---------------------|------------------|
| 3962 ft. to 170 ft. | Heavy Rotary mud |
| 170 ft. to 125 ft.  | 15 sacks cement  |
| 125 ft. to 25 ft.   | Heavy Rotary mud |
| 25 ft. to Surface   | 10 sacks cement  |

Well was plugged by Halliburton Oil Well Cementing Co. with supervision of Mr. Stough, State Plugger

RECEIVED  
Conservation

Conservation Div.

NOV 10 1948

STATE OF KANSAS  
COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Crown Oil Company, Inc.,  
Address 2421 Tenth St., Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton ss

Dan H. Cook

\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. ~~CROWN OIL COMPANY, Inc.~~

(Signature)

2421 Tenth St., Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of November 1948

My commission expires..... June 2, 1952

22-2625 2-48-15M

Notary Public.

**PLUGGING**  
FILE SEC 33 T 23 R 120  
BOOK PAGE 67 LINE B

CROWN OIL COMPANY, Inc.,  
2421 Tenth Street,  
Great Bend, Kansas

15-185-01265-0000  
Heyen #1  
SW/4, Sec. 33-23s-12w  
Stafford County, Kansas

TOTAL DEPTH: 3962'  
Commenced: 10-18-48  
Completed: 11-4-48  
Casing: 8 5/8" Cemented at 170 ft.

Figures indicate bottom of formation:

|      |    |      |                                 |
|------|----|------|---------------------------------|
| 0    | to | 20   | Clay                            |
| 20   |    | 70   | Sand                            |
| 70   |    | 110  | Shale                           |
| 110  |    | 140  | Sand                            |
| 140  |    | 170  | Lime, shell and shale           |
| 170  |    | 620  | Red shale and red bed           |
| 620  |    | 698  | Shale, shell and Anhydrite lime |
| 698  |    | 780  | Blue shale                      |
| 780  |    | 1350 | Shale and shells                |
| 1350 |    | 1540 | Salt                            |
| 1540 |    | 1925 | Shale and lime                  |
| 1925 |    | 1965 | Shale                           |
| 1965 |    | 2155 | Lime                            |
| 2155 |    | 2625 | Broken lime and shale           |
| 2625 |    | 3175 | Lime and shale                  |
| 3175 |    | 3436 | Broken lime and shale           |
| 3436 |    | 3752 | Lime                            |
| 3752 |    | 3780 | Lime and chert                  |
| 3780 |    | 3799 | Lime                            |
| 3799 |    | 3833 | Lime and chert                  |
| 3833 |    | 3892 | Shale, lime and chert           |
| 3892 |    | 3914 | Shale and lime                  |
| 3914 |    | 3962 | Lime                            |
|      |    | 3962 | TOTAL DEPTH                     |

Geologist Tops:

Elevation: ----- 1871' D.F.  
Lansing K.C. --- 3436'  
Viola ----- 3768'  
Simpson ----- 3842'  
Arbuckle ----- 3912'  
Total Depth ---- 3962'

\*\*\*\*\*


STATE OF KANSAS     )  
COUNTY OF BARTON    ) ss

I, the undersigned, being duly sworn on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

CROWN OIL COMPANY, Inc.

By Sam H. Cook

Subscribed and sworn to before me this 8th day of November, 1948.



Grace E. Jacobs  
Notary Public

My commission expires June 2, 1952

CROWN OIL COMPANY, Inc.,  
2421 Tenth Street,  
Great Bend, Kansas

15-185-01265-0000  
Heyen #1  
SW/4, Sec. 33-23s-12w  
Stafford County, Kansas

TOTAL DEPTH: 3962'  
Commenced: 10-18-48  
Completed: 11- 4-48  
Casing: 8 5/8" Cemented at 170 ft.

Figures indicate bottom of formation:

|      |    |      |                                 |
|------|----|------|---------------------------------|
| 0    | to | 20   | Clay                            |
| 20   |    | 70   | Sand                            |
| 70   |    | 110  | Shale                           |
| 110  |    | 140  | Sand                            |
| 140  |    | 170  | Lime, shell and shale           |
| 170  |    | 620  | Red shale and red bed           |
| 620  |    | 698  | Shale, shell and Anhydrite lime |
| 698  |    | 780  | Blue shale                      |
| 780  |    | 1350 | Shale and shells                |
| 1350 |    | 1540 | Salt                            |
| 1540 |    | 1925 | Shale and lime                  |
| 1925 |    | 1965 | Shale                           |
| 1965 |    | 2155 | Lime                            |
| 2155 |    | 2625 | Broken lime and shale           |
| 2625 |    | 3175 | Lime and shale                  |
| 3175 |    | 3436 | Broken lime and shale           |
| 3436 |    | 3752 | Lime                            |
| 3752 |    | 3780 | Lime and chert                  |
| 3780 |    | 3799 | Lime                            |
| 3799 |    | 3833 | Lime and chert                  |
| 3833 |    | 3892 | Shale, lime and chert           |
| 3892 |    | 3914 | Shale and lime                  |
| 3914 |    | 3962 | Lime                            |
|      |    | 3962 | TOTAL DEPTH                     |

Geologist Tops:

Elevation: ----- 1871' D.F.  
Lansing K.C. --- 3436'  
Viola ----- 3768'  
Simpson ----- 3842'  
Arbuckle ----- 3912'  
Total Depth ---- 3962'

\*\*\*\*\*

STATE OF KANSAS )  
COUNTY OF BARTON ) ss

I, the undersigned, being duly sworn on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

CROWN OIL COMPANY, Inc.

By Sam H. Cook

Subscribed and sworn to before me this 8th day of November, 1948.

Charles E. Jacobs  
Notary Public

My commission expires June 2, 1952