


15-185-19387-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Stafford County. Sec. 34 Twp. 23 Rge. 12W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SE NE
Lease Owner National Drilling Company, Inc.
Lease Name Gerdes Well No. 1
Office Address 535 Petroleum Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4/15/60 19__
Application for plugging filed 4/15/60 19__
Application for plugging approved 4/15/60 19__
Plugging commenced 4/15/60 19__
Plugging completed 4/15/60 19__
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St. John, Stafford, Kansas.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3855 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8- 5/8	200'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole from Total Depth, 3855, to 180'; Set 1st plug at 180' with 20 sx. cement; Filled hole with mud from 1st plug to 40'; Set 2nd plug at 40' with 10 sx. cement; Filled hole from 2nd plug to Surface with Mud.

4-21-60
RECEIVED
CONSERVATION COMMISSION
APR 21 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor National Drilling Company, Inc.
Address 535 Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Howard A. Stoskopf (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Howard A. Stoskopf
535 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of April, 1960

My commission expires 2/23/64

Betty Baker
Betty Baker
Notary Public.

DRILLERS LOG

15-185-19387-0000

Gerdes No. 1

CASING RECORD:
8 5/8" @ 200'
w/185 sx. Sunset Cement.

COMPANY: National Drlg. Company, Inc.
CONTRACTOR: National Drlg. Company, Inc.
COMMENCED: April 7, 1960
COMPLETED: April 16, 1960

DESCRIPTION: SW SE NE
34-23-12
Stafford Co.,
Kansas
ELEVATION: 1859 GL
1861 DF
1864 KB

TOTAL DEPTH: 3855 (-1991)

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Clay	0	30
Sand=	30	130
Shale & Shells	130	635
Anhydrite	635	670
Shale & Shells	670	1575
Lime & Shale	1575	2005
Lime	2005	2260
Lime & Shale	2260	2710
Shale & Shells	2710	2890
Shale & Lime	2890	2995
Lime	2995	3270
Shale	3270	3383
Lime	3383	3855

I certify that this is a true and correct copy of the above log to the best of my knowledge.

NATIONAL DRILLING COMPANY, INC.

Howard A. Stoskopf
Howard A. Stoskopf

Subscribed and sworn to before me this 17 day of April, 1960.

Betty Baker
Notary Public

My Commission Expires 2/23/64.

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1960
CONSERVATION DIVISION
Wichita, Kansas