


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.



Locate well correctly on above
Section Plat

Stafford County, Sec 34 Twp 23 Rge 12 (E) (W)
Location as "NE1/4NW1/4SW1/4" or footage from lines NE NE NW
Lease Owner Crown Oil Company, Inc.
Lease Name Varning Well No. 1
Office Address Odell at Tenth St., Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 11-22-48 19
Application for plugging filed 11-22-48 19
Application for plugging approved 11-22-48 19
Plugging commenced 11-22-48 19
Plugging completed 11-22-48 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Stough
Producing formation Depth to top Bottom Total Depth of Well 3864 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3864' to 177' Heavy rotary mud
One plug at 177' with 15 sacks cement,
then heavy rotary mud to 35' with
One plug with 10 sacks cement

RECEIVED

NOV 27 1948 11-27-48

STATE CORPORATION COMMISSION
KANSAS

STATE CORPORATION COMMISSION
NOV 26 1948

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Crown Oil Company, Inc.,
Address Odell at Tenth St., Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) *Sam D. Gresh*
CROWN OIL CO., Inc., Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of November, 1948

Graue C. Jacobs
Notary Public.

My commission expires June 2, 1952

22-2825 2-48-15M
PLUGGING
FILE SEC 34 T 23 R 12W
BOOK PAGE 49 LINE 34

15-185-01231-0000

CROWN OIL COMPANY, Inc.,
Odell at Tenth Street,
Great Bend, Kansas

Verning #1
NE NE NW, Sec. 34-23-12W
Stafford County, Kansas

ROTARY T.D. 3864 ft.
Commenced: 11-5-48
Completed: 11-22-48
Casing: 8 5/8" at 177 ft.

Elevation: 1863 D.F.
Lansing: 3420
Viola: 3736
Simpson: 3790
Arbuckle: 3854
Rotary T.D.: 3864

0	to	25	surface soil and sandy clay
25		40	sand
40		177	sand and shale
177		455	shale and shells
455		662	Red Bed and shale
662		685	Anhydrite lime
685		770	Shale and shells
1165		1255	Red shale
1255		1400	Salt and lime
1400		1495	Lime with shale streaks
1495		1550	Shale and shells
1550		1640	Lime with shale breaks
1640		1775	Broken lime
1775		1830	Hard lime
1830		2035	Lime
2035		2240	Lime and shale
2240		2530	Lime with shale breaks
2530		2665	Shale
2665		2760	Shale and lime
2760		2810	Shale
2810		2990	Shale and shells
2990		3200	Shale and lime
3200		3290	Lime
3290		3355	Lime and shale
3355		3420	shale
3420		3455	Broken lime and shale
3455		3485	Lime
3485		3530	Lime and shale breaks
3550		3700	Lime
3700		3745	Shale and lime
3745		3785	Lime
3785		3853	Shale and Lime
3853		3864	Lime
		3864	Total Depth

RECEIVED
NOV 27 1948
STATE REGISTRATION
COMMISSION
KANSAS

STATE OF KANSAS)
COUNTY OF BARTON) ss

I, the undersigned, being duly sworn on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

CROWN OIL COMPANY, Inc.

By *Sam H. Clark*

Subscribed and sworn to before me this 24th day of November, 1948.

PLUGGING
FILE SEC 34-23-12W
BOOK PAGE 69 LINE 34

Ernest C. Jacobs
Notary Public

My commission expires June 2, 1952