

15-185-60290-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 31 Twp. 23 Rge. 12 (E) (W) X

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Misco Supply Company
Lease Name Hartnett Well No. I
Office Address 200 Misco Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed 7-25-69 19____
Application for plugging approved 7-26-69 19____
Plugging commenced 8-11-69 19____
Plugging completed 8-19-69 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3890 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	187	None
				5 1/2	None	2927

RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1969
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in. Cleaned out cellar.

Sanded to 3500'. Dumped 5 sacks of cement. Rigged up jacks. Working pipe. Shot pipe at 3100' and 2910'.

Pulling pipe.

Squeezed well with 15 sacks of mud and 75 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of August, 1969

My commission expires May 27, 1973

Glen D. [Signature]
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-195-00290-0000


COPY

Company- BOB DOUGLAS
Farm-Hartnett No. 1

SEC. 34 T. 23 R. 12W
NE NE SE

Total Depth. 3890'
Comm. 10-15-59 Comp. 11-9-59
Shot or Treated.
Contractor. Nat'l Drlg. & Carter Drlg.
Issued. 2-27-60

County Stafford
KANSAS



Elevation. 1859 DF

Production. 28 BOPH

CASING:

8 5/8" 187' cem. w/165 sx.
5 1/2" 3648' cem. w/40 sx.

Figures indicate Bottom of Formations.

clay & sand	125
sand	130
red bed	185
shale & red bed	275
red bed & shale	640
anhydrtie	660
shale & shells	1260
shale & lime	1635
lime & shale	2400
shale & shells	2660
shale & lime	2900
lime & shale	3025
lime & chalk	3170
lime	3750
lime & chert	3793
lime	3890
Total Depth	

TOPS:

Anhydrite	640
Heebner	3226
Toronto	3242
Douglas	3260
Brown Lime	3380
Lansing	3403
Base Kansas City	3674
Viola	3742
Simpson	3791
Arbuckle	3855

DST 3481-3506 Open 60 min. Strong
blow Rec. 70' of oil sptd. wty. mud,
60' oil sptd. mdy. wtr., 180' mdy.
s.w. ISIP 1180#/15", FBHP 800#/20"
FP 40-110#.

DST 3536-3615 Open 60 min. Shut-in
20 min. Rec. 1635' gas, 1350' frgy.
oil, 30' OCM, ISIP 1350#, FBHP 1110#,
FP 400-520#.

DST 3744-3797 Open 90 min. weak blow,
Rec. 90' drilling mud, 60' wtry.
mud. sso in btm. of tool, ISIP
1380#/15", FBHP 1130#/30", FP 0-100#

Perf. 24/3538-44 Treated w/500 gal.
reg. & 1500 gal. retarded acid.

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1969
CONSERVATION DIVISION
Wichita, Kansas

3230