

OR
FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Strike out upper line
when reporting plug-
ging of formations.

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 1 Twp. 23 SRge. (E) 13(W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SW-NE
Lease Owner Edward M. Swearer
Lease Name Witt Well No. 1
Office Address 306 Union National Bank Building
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed December 30 1945
Application for plugging filed December 30 1945
Application for plugging approved December 30 1945
Plugging commenced December 30 1945
Plugging completed December 30 1945
Reason for abandonment of well or producing formation dry hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well H. W. Kerr
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3840 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was filled with mud from 3840' to 300', wooden plug placed at 300', 15 sacks cement, mud laid in fluid to 40' wooden plug placed at 40', 10 sacks cement to top of hole



(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Edward M. Swearer
Address 306 Union National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Edward M. Swearer (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edward M. Swearer

Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16th day of January, 1946

Margie Fisher Notary Public.

My commission expires August 31, 1946

15-185-01143-0000

SWEARER ET AL
 No. 1 WITT
 SW SW NE Sec. 1 Twp. 23 Rge. 13W
 Stafford County, Kansas

Rigging up 12-13-45

Ran 320' of 8 5/8" surface casing -
 cemented with 175 sacks cement

Formation	From	To		
Sand	0	115		
Clay and shells	115	210		
Red rocks and shale	210	250		
Red Bed	250	330		
Red Bed and shell	330	450		
Shale and shells	450	1205		
Shale and lime	1205	1610		
Shale and shell	1610	1680	Top Lansing	3393
Shale and lime	1680	1800	Top Viola	3699
Lime	1800	1935	Top Simpson	3747
B lack lime	1935	2000	Top Arbuckle	3803
Lime	2000	2140		
Lime and shale	2140	2190		
Lime	2190	2223		
Shale and lime	2223	2700		
Lime	2700	2765		
Shale and lime	2765	2845		
Lime	2845	2910		
Shale	2910	2948		
Lime	2948	3045		
Shale	3045	3060		
Lime	3060	3294		
Lime and shale	3294	3365		
Shale	3365	3387		
Lime	3387	3640		
Lime and shale	3640	3660		
Shale	3660	3675		
Lime and shale	3675	3719		
Lime and chert	3719	3740		
Chert and shale	3740	3758		
Sand and shale	3758	3796		
Lime and shale	3796	3834		
Lime	3834	3840 T.D.		

I, Edward M. Swearer, do solemnly swear that the above log is true and correct to the best of my knowledge.

Edward M. Swearer

Subscribed and sworn to before me this 16th day of January, 1946.

My comm. exp.
 August 31, 1946

Maxine Fisher

1 23 13W
 40 38