

To be filed with State Corp Comm.

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15 - 145 - 21,204-0000 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Zenith Drilling Corporation OPERATORS LICENSE NO. 5141
505 Fourth Financial Center
ADDRESS Wichita, Kansas 67202 PHONE # (316) 265-6697

LEASE (FARM) Smith WELL NO. 1 WELL LOCATION NW NE COUNTY Pawnee
SEC. 6 TWP. 22S RGE. 20 ~~XXXX~~(W) TOTAL DEPTH 4462' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A XX SWD or INJ WELL _____ DOCKET NO. _____
SURFACE CASING SIZE 8 5/8" SET AT 388' KB CEMENTED WITH 250 SACKS
CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
PERFORATED AT _____

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Fill hole with heavy mud, plugged
through open ended drill pipe. 50 sacks at 1360'; 70 sacks at 840'; 40 sacks at 420'; 1/2
sack hulls, plug and 10 sacks at 40'; 15 sacks in rat hole, 10 sacks in mouse hole. Used
60/40 Pozmix plug 4% gel - total 6% - and 3% cc.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 2:00 PM, 7-16-85

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Jim Shriner PHONE # (316) 278-2131
ADDRESS P. O. Box 129, Sterling, Kansas 67579

RECEIVED
STATE CORPORATION COMMISSION
7-22-85
7:11 22
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING CONTRACTOR Sterling Drilling Company LICENSE NO. 5142
P. O. Box 129
ADDRESS Sterling, Kansas 67579 PHONE # (316) 278-2131

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
(Operator or Agent)
F. A. Wuellner, Secretary
DATE: July 17, 1985