

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-02985-00-00
Spot: NESWNW Sec/Twnshp/Rge: 5-14S-17W
3594 feet from S Section Line, 4397 feet from E Section Line
Lease Name: PFEIFER B LEASE Well #: 1
County: ELLIS Total Vertical Depth: 3604 feet

Operator License No.: 34318

String Size Depth (ft) Pulled (ft) Comments

Op Name: BEREXCO LLC

PROD 5.5 3551 100 SX

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

SURF 10.75 197 125 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/15/2017 10:00 AM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: CURT GABEL

Company: BEREXCO LLC

Phone: (785) 623-0546

Proposed Plugging Method: Ordered 475 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Squeezed at 648' and 750' w/750 sx cement, 2874' - 2900' w/175 sx cement.
Production perforations: 3333' - 3337', 3551' - 3604'.

Plugging Proposal Received By: RICHARD WILLIAMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/15/2017 12:20 PM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 3450' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 2498' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1592' and pumped 115 sx cement. Pulled tubing to 594' and pumped 110 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing with 15 sx cement. Hooked to 10 3/4" x 5 1/2" annulus and pumped 10 sx cement. Shut in pressure 200 psi.

GPS: 38.86653N -099.24039W

Remarks: GLOBAL OILFIELD SERVICES TICKET # 2818

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

MAR 13 2017

CONSERVATION DIVISION
WICHITA, KS

INVOICED

Form CP-2/3

FEB 23 2017

MAR 21 2017