

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01303-00-00
Spot: NWNENENW Sec/Twnshp/Rge: 14-24S-12E
5100 feet from S Section Line, 3000 feet from E Section Line
Lease Name: SULLIVAN Well #: 29
County: GREENWOOD Total Vertical Depth: 1796 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1738		100 SX
SURF	8.625	135		100 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/09/2017 10:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Rcvd. from: DWAIN STOUT Company: Phone: (316) 640-9072

Proposed Pump gel from TD into casing. Set 50 ft. cement plug at bottom of casing. Shoot off casing at 800 ft. Set a 50 ft. cement
Plugging plug at 800 ft. Pull tubing to 150 ft. and cement to surface.
Method:

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2017 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 1700', pumped 20 sxs cement, pull tubing to 800', pumped 20 sxs cement, pulled tubing to 150', pumped 60 sxs cement to surface, gel spacers between cement plugs, casing shot @ 800' & 150'.

RECEIVED
KCC DIST # 3
FEB 27 2017
CHANUTE, KS

mtt

Remarks:

Plugged through: TBG

District: 03

Signed

Mike Heffern

(TECHNICIAN)

KCC WICHITA

MAR 06 2017

RECEIVED

INVOICED Form CP-2/3

MAR 21 2017

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **3161**
Foreman KEVIN M. COY
Camp EUREKA

API # 15-073-01303-00-00

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
2-9-17	1046	SULLIVAN #29	14	24S	12E	GW	KS
Customer <u>R.R.A. INC.</u>			Safety Meeting <u>KM</u> <u>RL</u> <u>GM</u>	Unit # <u>102</u> <u>114</u> <u>145</u> <u>120 P.U.</u>	Driver <u>RIK L.</u> <u>KEVIN M.</u> <u>KEVIN M</u> <u>GREG M.</u>	Unit #	Driver
Mailing Address <u>100 S. MAIN ST. STE 510</u>							
City <u>Wichita</u>	State <u>KS</u>	Zip Code <u>67202</u>					

Job Type P.T.A. OLD WELL Hole Depth 1796 Slurry Vol. 25 BBL TOTAL Tubing _____
Casing Depth 1738 Hole Size _____ Slurry Wt. _____ Drill Pipe _____
Casing Size & Wt. 5 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY MEETING: RAN 2 3/8 TUBING IN 5 1/2 CASING. SPOT CEMENT PLUGS AS FOLLOWING.
(5 1/2 PERFORATED @ 800' & @ 150')

20 SKS @ 1700' w/ HULLS

GEL SPACER

20 SKS @ 800'

GEL SPACER

60 SKS 150' TO SURFACE ON ID & ANNULUS OF 5 1/2

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge	750.00	750.00
C 107	80	Mileage	3.95	79.00
C 203	100 SKS	60/40 Pozmix Cement	12.75	1275.00
C 206	350 "	Gel 4%	.20 "	70.00
C 206	500 "	Gel SPACER	.20 "	100.00
C 214	40 "	Hulls	.45 "	18.00
C 108A	4.3 TONS	Ton Mileage	M/C	345.00
C 113	3 HRS	80 BBL VAC. TRUCK	85.00	255.00
KCC WICHITA				
MAR 06 2017				
RECEIVED				
THANK YOU			Sub TOTAL	2892.00
M			Less 5%	155.45
7.5%			Sales Tax	216.91
				2953.46

Authorization WITNESSED BY DWAIN STOUT Title _____ Total 2953.46
KCC AGENT MIKE HEFFERN

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.