

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-21829-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 28-33S-2E
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HASLET Well #: 1
County: SUMNER Total Vertical Depth: 3736 feet

Operator License No.: 32346
Op Name: B5 OPERATING, LLC
Address: PO BOX 45
WELLINGTON, KS 67152

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3506		100 SX
SURF	8.625	250		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/15/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: MITCH BARTELSON Company: B5 OPERATING, LLC Phone: (620) 326-0486

Proposed Plugging Method: AS PER KCC RULES & REGULATIONS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 02/15/2017 11:00 AM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP SET @ 3310' AND CAPPED WITH 2 SX. OPERATOR STATED ON PLUGGING APPLICATION THERE WAS A PROBABLE CASING LEAK ABOVE THE PERFORATIONS SK SO ANOTHER CIBP WAS SET @ 1025' CAPPED W/2SX. WAITED FOR IT TO SET UP. LOADED 4.5" AND PRESSURE TESTED CASING TO 300 PSIG. FOR 15 MINUTES WITH NO DROP IN PRESSURE. PERFORATED 4.5" @ 300', RAN TUBING IN CIRCULATED 120 SX OF COMMON CEMENT TO SURFACE. TOPPED OFF CASING AND RETURNED ON 2/20/17 TO VERIFY CEMENT STAYED TO SURFACE. CUT OFF CASING BELOW GROUND AND GRADED SURFACE. COMMON CLASS A CEMENT.

Perfs:

Top	Bot	Thru	Comments
3373	3394	TBG	

Remarks: CEMENT TICKET #6604

Plugged through: TBG

District: 02

Signed _____

Daniel J. Fox
(TECHNICIAN)

INVOICED

MAR 28 2017

Form CP-2/3