

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-165-21628-00-00

Spot: NWSENE

Sec/Twnshp/Rge: 29-18S-20W

4302 feet from S Section Line,

340 feet from E Section Line

Lease Name: REITZ #2 LEASE

NCRA Well #: 2

County: RUSH

Total Vertical Depth: 4325 feet

Operator License No.: 34318

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4232	0	WITH 165 SX CMT
SURF	8.625	1375		WITH 500 SX CMT

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/21/2017 10:00 AM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Revd. from: MARK LEIKER

Company: BEREXCO LLC

Phone: (316) 772-8649

Proposed
Plugging
Method:

PUMP BOTTOM WITH 60 SX CMT & 200# HULLS. IF WELL WON'T PRESSURE UP SET CIBP @ 1500'.
PERFORATE AT 1400' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 03/21/2017 3:30 PM

KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

PUMPED BOTTOM WITH 60 SX CMT & 200# HULLS. HELD PRESSURE AT 300#. PULLED TBG. SET CIBP @ 1500'. PERFORATED AT 1400'. PUMPED DOWN CASING. CIRCULATED 320 SX CMT TO SURFACE IN AND OUT 5 1/2" X 8 5/8" ANNULUS.

Top	Bot	Thru	Comments
4112	4116	CSG	

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
MAR 22 2017
KCC DODGE CITY

INVOICED

MAR 28 2017

Form CP-2/3

KMS