

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-22783-00-00  
Spot: SENENWNE Sec/Twnshp/Rge: 13-26S-4E  
4830 feet from S Section Line, 1470 feet from E Section Line  
Lease Name: MABRY B Well #: 3  
County: BUTLER Total Vertical Depth: 2490 feet

Operator License No.: 35294  
Op Name: L V OIL, LLC  
Address: 801 FREDRICK DR.  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2489		139 SX
SURF	8.625	215		135 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/16/2017 12:00 AM  
Plug Co. License No.: 31538 Plug Co. Name: BURKHOLDER, STEVE DBA HAD-A-CALL OIL  
Proposal Rcvd. from: VIC BUTLER Company: L V OIL, LLC Phone: (316) 323-7900

Proposed Plugging Method: Find TD with wireline. Set tubing approximately 50' above top perf. Have Consolidated Well Service pump approximately 20 sacks of cement on bottom. Pull tubing out and run wireline to check top of cement. Then have Cornish Wireline Service shoot holes in casing at approximately 250'. Run tubing to 250 feet and have Consolidated pump cement down and up the backside until both inside and outside casing are full. Cut off casing 3' below ground level and clean up location.

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/17/2017 12:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

- 1) Ran in tubing to 2422', spotted 20 sks 60/40/4% cement. Fluid circulated. Pulled tubing out of hole.
- 2) Wait 2 hrs, ran in with wireline and tagged plug at 2130'
- 3) Loaded hole, stayed full -- ran in with wireline and perf'd at 265'. Cut window in surface casing to circulate.
- 4) Tied into 5.5" casing, pumed 17 bbls water w/ dye. Full returns.
- 5) Pumped 110 sks 60/40/4% cement, circulated cement to surface.

2/18/2017: Checked top plug next day, cement level down <1', good to cut down casing and bury.

Perfs:

Top	Bot	Thru	Comments
2452	2459		

Remarks: CEMENTING COMPLETED BY ELITE CEMENTING. EUREKA, KS. TICKET #: 3167. PLUGGED DUE TO COMPLIANCE W/ 82-3-111 --- DENIED TA

Plugged through: TBG

District: 02

Signed Jonathan Hill

(TECHNICIAN) INDEXED

MAR 28 2017

Form CP-2/3

14