

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-069-20371-00-00  
Spot: NWSESWNW Sec/Township/Rge: 13-26S-30W  
3244 feet from S Section Line, 4494 feet from E Section Line  
Lease Name: BLEUMER Well #: 1-13  
County: GRAY Total Vertical Depth: 6200 feet

Operator License No.: <u>5144</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>MULL DRILLING COMPANY, INC.</u>	CIBP		5700		
Address: <u>1700 N WATERFRONT PKWY BLDG 12</u> <u>WICHITA, KS 67206</u>	PC		1915		CEMENTED WITH 220 SX CMT. 20 SX CMT CIRCULATED TO PIT.
	PROD	5.5	6161	0	WITH 350 SX CMT
	SURF	8.625	464		WITH 350 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/02/2017 10:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: TIM HOSS Company: MULL DRILLING Phone: (785) 798-2300

Proposed Plugging Method: PUMP BOTTOM WITH 50 SX CMT & 200# HULLS. GEL SPACER TO 2185' CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/06/2017 3:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

EXISTING BRIDGE PLUG AT 5700'. 3/2/17: PUMPED 20 SX CMT DOWN ANNULUS.  
PUMP BOTTOM WITH 50 SX CMT & 200# HULLS GEL SPACER TO 2185'. PUMPED  
180 SX CMT BUT DID NOT PRESSURE UP. SHUT DOWN TO STATIC OUT. 3/6/17:  
ESTIMATED TOC AT 220'. TOPPED OFF WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5745	5750		
5012	5020		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED  
MAR 17 2017  
KCC DODGE CITY

Signed [Signature]  
(TECHNICIAN)  
INVOICED

MAR 28 2017

KMS  
Form CP-2/3