

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25945-00-00
Spot: SENWNWNW Sec/Twnshp/Rge: 31-19S-21W
471 feet from N Section Line, 426 feet from W Section Line
Lease Name: KEN & TRAVIS SCHABEN Well #: 1-31
County: NESS Total Vertical Depth: 4530 feet

Operator License No.: <u>35033</u>	<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comments</u>
Op Name: <u>SCHABEN OIL LLC</u>	SURF	8.625	267		WITH 170 SX CMT
Address: <u>2704 ASH</u>					
<u>HAYS, KS 67601</u>					

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/14/2017 6:30 PM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Revd. from: SID DEUTSCHER Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 730' WITH 80 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: WADE KLAUS WitnessType: NONE
Date/Time Plugging Completed: 03/14/2017 8:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

Perfs:

1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 730' WITH 80 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY.

Plugged through: DP

District: 01

Signed



(TECHNICIAN)

RECEIVED
MAR 17 2017
KCC DODGE CITY

INVOICED
MAR 28 2017

Form CP-2/3

12M5