

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-20376-00-00
Spot: NWSESWSE Sec/Twnshp/Rge: 25-34S-13W
634 feet from S Section Line, 1894 feet from E Section Line
Lease Name: HARDTNER HOMES Well #: 2
County: BARBER Total Vertical Depth: 4970 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4970	0	WITH 125 SX CMT
SURF	8.625	207		WITH 170 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/20/2017 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: RUN TBG TO TOP OF FISH @ 4760' & SPOT 100# HULLS & 25 SX CMT. PLUG AT 650' WITH 10 SX GEL & 50 SX CMT. PLUG AT 240' WITH 40 SX CM.T PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: PARTIAL
Date/Time Plugging Completed: 03/21/2017 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

****WASN'T ENOUGH FREE 4 1/2" CASING TO RECOVER. ONLY HAD 5" OF STRETCH**** RUN TBG IN TO 4730' & SPOT 100# HULLS & 25 SX CMT. PERFORATE 4 1/2" CASING AT 600'. RUN TBG INTO 600'. PUMP DOWN TBG WITH 200 SX FILLING 4 1/2" CASING WITH CMT TO SURFACE. LOST RETURNS ON 4 1/2" X 8 5/8" ANNULUS. SDON. 3/21/17: TAG TOC @ 65' INSIDE & OUTSIDE OF 4 1/2" CASING. TOP OFF INSIDE AND BACKSIDE OF 4 1/2" CASING WITH 45 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4805	4834		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: TBG

District: 01

Signed Stephen Pfeifer
(TECHNICIAN)

RECEIVED
MAR 22 2017
KCC DODGE CITY

INVOICED
MAR 28 2017

Form CP-2/3

KMS